

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS-3	WILL.	305	128
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
RSCH 02 OF 02				

SHEET	STATION	OFFSET (FT)	CONCRETE HEADWALL REMOVAL (EACH)	REMOVAL ( R )					ADJUST (ADJ)			STORM SEWER TO BE PLUGGED (CU YDS)	DRAIN. STRUCTURES TO BE CLEANED ( C ) (EACH)	STORM SEW./BOX CULVERT TO BE CLEANED (CLN) (FT)			
				CB (EACH)	MH (EACH)	PRC FES (EACH)	STORM SEWER				MEDIAN INLET BOX				CB (EACH)	MH (EACH)	RECON MH (EACH)
							12"	15"	18"	24"							
DRU-09	912+00	CL															
DRU-09	913+10	CL												1	30X19	174	
DRU-09	914+00	CL													24"	192	
DRU-09	915+10	CL												1	18"	154	
DRU-09	916+00	CL												1	15"	173	
DRU-09	916+70	CL												1	15"	112	
DRU-09	918+00	CL												1	12"	193	
DRU-09	918+45	CL												1	12"	293	
DRU-09	919+00	CL												1	12"	143	
DRU-09	919+70	CL												1	12"	108	
DRU-09	920+00	CL												1	15"	13	
DRU-09	921+70	CL												1	24"	144	
DRU-10	923+00	CL															
DRU-10	924+75	CL															
DRU-10	925+50	CL															
DRU-10	926+15	CL															
DRU-10	928+00	CL															
DRU-10	928+50	CL															
DRU-10	929+20	CL															
DRU-10	929+25	CL															
DRU-10	929+32	100' L															
DRU-10	929+32	64' L															
DRU-10	929+32	64' L															
DRU-10	929+32	65' R															
DRU-10	929+32	CL													18X30	57	
DRU-10	929+32	100' R													24"	84	
DRU-10	930+35	CL												1	12"	108	
DRU-10	931+00	CL												1	12"	108	
DRU-10	931+50	CL												1	18"	108	
DRU-10	932+00	CL												1	18"	108	
DRU-10	932+65	CL												1	18"	108	
DRU-10	933+00	CL												1	21"	108	
DRU-10	933+80	CL												1	21"	103	
DRU-10	934+25	CL												1	21"	34	
DRU-10	934+95	CL												1	15"	19	
DRU-10	935+50	CL												1	24X24	66	
DRU-10	936+10	CL												1	30"	58	
DRU-11	937+00	CL															
DRU-11	937+25	CL															
DRU-11	937+40	CL															
DRU-11	937+50	CL												1	15"	29	
DRU-11	937+70	CL													21"	18	
DRU-11	937+70	CL													21"	138	
DRU-11	937+70	70' L															
DRU-11	937+70	70' R															
DRU-11	937+75	CL															
DRU-11	938+10	CL															
DRU-11	939+00	CL															
DRU-11	939+60	CL												1	15"	138	
DRU-11	940+50	CL												1	15"	139	
DRU-11	941+05	CL												1	12"	138	
DRU-11	942+00	CL												1	15"	108	
DRU-11	942+50	CL												1	15"	108	
DRU-11	943+50	CL												1	18"	108	
DRU-11	944+00	CL												1			
DRU-11	947+00	CL												1			
DRU-11	947+50	CL												1			
DRU-11	948+10	CL												1			
DRU-11	948+50	CL												1			
DRU-11	949+30	CL												1			
DRU-11	950+00	CL												1			
DRU-11	950+40	CL												1			
DRU-12	1906+00	57' R	1														
TOTALS			3	0	3	5	0	0	0	64	9	0	1	3	4.6	27	

STORM SEWER SUBTOTAL = 4559  
 BOX CULVERT SUBTOTAL = 1318



SMITH ENGINEERING CONSULTANTS, INC.  
 www.smithengineering.com

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 55  
 143RD STREET TO WEBER ROAD

DRAINAGE SCHEDULE -  
 REMOVALS  
 (2 OF 2)

SCALE: 1" = 50'  
 DATE: 02/23/2007

DRAWN BY JPA  
 CHECKED BY TEH