CONTRACT NO. 60B47

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-3	WILL	305	129
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SSCH 01 OF 02

STRUCTURE NUMBER	SHEET NUMBER	LOCATION			MANHOLES TYPE A TY 1 F CL			PRECAST F.E.S. 24"		DRAINAGE STRUCTURE TY 8X3, W/TWO TY 20 F&G	CATCH BASINS TYPE A TYPE 20 FRAME & GRATE			DRAINAGE STRUCTURE SPECIAL W/ TY 20 F&G	RIM ELEV	INVERT ELEVATIONS							
		STATION	OFFSET (FT)	SIDE	4 FT	5 FT	6 FT	24"	E.R.S. 24"		4 FT	5 FT	6 FT			NORTH	SOUTH	EAST	WEST	SOUTH EAST	NORTH EAST	SOUTH WEST	NORTH WEST
201	DRU 1	792+00	0.5	LT							1				628.68						624.95		
200	DRU 1	792+00	3.5	RT							1				629.13						624.68		
203	DRU 1	795+00	0.5	LT							1				627.69						623.63	623.63	
202	DRU 1	795+00	3.5	RT								1			627.95						623.73	623.73	
205	DRU 1	797+49.87	0.5	LT							1				626.80						623.00	623.00	
204	DRU 1	797+49.87	3.5	RT								1			626.84						622.93	622.93	
207	DRU 1	798+38.55	0.5	LT							1				626.68						622.45	622.83	
206	DRU 1	798+38.55	3.5	RT								1			626.49						622.70	622.70	
209	DRU 1	799+25.64	0.05	LT							1				626.58						622.39	622.39	
208	DRU 1	799+50	2.6	RT								1			626.10						622.48	622.48	
211	DRU 1	799+99.90	1.1	LT							1				626.52						622.34	622.34	
210	DRU 1	800+00	1.9	RT								1			626.01						622.42	622.42	
213	DRU 1	800+90.68	1.5	LT							1				626.61						622.28	622.28	
212	DRU 1	800+92.05	1.5	RT								1			625.90						622.31	622.31	
215	DRU 1	801+71.72	1.5	LT							1				626.67						622.21	622.21	
214	DRU 1	801+75	1.5	RT		1									625.77						622.21	622.21	
217	DRU2	802+56.77	1.5	LT							1				626.68						622.16	622.16	
216	DRU2	802+59.85	1.5	RT								1			625.72						622.15	622.15	
219	DRU2	803+28.82	1.5	LT							1				626.65						622.11	622.11	
218	DRU2	803+28.82	1.5	RT								1			625.68						622.10	622.10	
221	DRU2	803+90.94	1.5	LT							1				626.61						622.06	622.06	
220	DRU2	803+90.94	1.5	RT								1			625.66						622.05	622.05	
223	DRU2	804+67.29	1.5	LT							1				626.56						622.01	622.01	
222	DRU2	804+67.29	1.5	RT								1			625.66						622.00	622.00	
225	DRU2	805+46.93	1.5	LT							1				626.52						621.95	621.95	
224	DRU2	805+46.93	1.5	RT								1			625.61						621.94	621.94	
250	DRU2	806+33.94	1.5	RT								1			625.48						621.88	621.88	
227	DRU2	806+34.58	1.5	LT							1				626.43						621.89	621.89	
229	DRU2	807+03.72	1.5	LT							1				626.45						621.84	621.84	
228	DRU2	807+03.72	1.5	RT								1			625.43						621.83	621.83	
231	DRU2	807+70.92	1.5	LT							1				626.43						621.79	621.79	
230	DRU2	807+74.36	1.5	RT								1			625.40						621.78	621.78	
233	DRU2	808+15.85	1.5	LT							1				626.45						621.76	621.76	
232	DRU2	808+15.85	1.5	RT								1			625.39						621.75	621.75	
235	DRU2	808+76.81	1.5	LT							1				626.39						621.72	621.72	
234	DRU2	808+76.81	1.5	RT								1			625.39						621.71	621.71	
236	DRU2	809+50.22	1.5	LT							1				626.24			621.67				621.67	
237	DRU2	809+60	1.5	RT								1			625.47				621.65		621.65	621.65	
238	DRU2	809+75	1.5	RT											625.61						621.64	621.64	
240	DRU2	810+54.06	1.5	LT							1				626.62					622.39			
239	DRU2	810+54.47	1.5	RT							1				625.61						621.85	621.85	622.35
242	DRU2	811+50	1.5	LT							1				626.77					622.44			
241	DRU2	811+50.09	1.5	RT							1				625.84						622.15	622.15	622.40
243	DRU2	812+00	1.5	RT							1				625.94						622.32	622.32	
245	DRU2	814+50	1.5	LT							1				627.78					623.40			
244	DRU2	814+50	1.5	RT							1				626.74						623.11	623.36	623.36
247	DRU2	817+00	1.5	LT							1				628.11					624.25			
246	DRU2	817+00	1.5	RT							1				627.25						624.23		624.23
249	DRU3	820+00	1.5	LT							1				627.95					623.57			
248	DRU3	820+00	1.5	RT							1				627.03						623.54		623.54
251	DRU3	821+50	1.5	LT							1				627.58					623.09			
250	DRU3	821+50	1.5	RT							1				626.80						623.06	623.06	623.06
REC	DRU3	821+70	3.0	RT											626.78				622.99	622.99			622.68
253	DRU3	824+50	1.5	LT								1			626.85						618.76		
252	DRU3	824+50	1.5	RT								1			626.04						616.92		
255	DRU3	827+50	1.5	LT								1			624.34					617.81			617.81
254	DRU3	827+50	1.5	RT								1			623.42					616.61	616.61		
257	DRU3	830+50	1.5	LT								1			621.50					617.20			617.20
256	DRU3	830+50	1.5	RT								1			620.63						616.31	616.31	
258	DRU3	831+75	1.5	LT								1			620.67						616.95	616.95	
259	DRU3	831+92.50	1.5	RT								1			619.75						616.17	616.17	
260	DRU4	832+39.61	1.5	LT								1			620.60						616.82	616.82	
261	DRU4	832+95.00	1.5	LT								1			620.47						616.71	616.71	
262	DRU4	833+39.22	1.5	RT								1			619.42						616.08	616.08	
263	DRU4	833+68.95	1.5	LT								1			620.43						616.62	616.62	
264	DRU4	834+11	1.5	RT								1			619.43						616.03	616.03	
265	DRU4	834+60.36	1.5	LT								1			620.34						616.51	616.51	
266	DRU4	834+92.87	1.5	RT								1			619.45						615.97	615.97	
267	DRU4	835+34.30	1.5	LT								1			620.34						616.42	616.42	
268	DRU4	835+65.66	1.5	RT								1			619.45						615.92	615.92	
269	DRU4	836+12.94	1.5	LT								1			620.36						616.26	616.26	
270	DRU4	836+44.43	1.5	RT								1			619.48						615.87	615.87	
271	DRU4	836+75.70	1.5	LT								1			620.33						616.13	616.13	
272	DRU4	837+20.33	1.5	RT								1			619.50						615.82	615.82	
273	DRU4	837+47	1.5	LT								1			620.38						615.98	615.98	

PARSONS BRINCKERHOFF

SMITH ENGINEERING CONSULTANTS, INC.
www.smithengineering.com

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
143RD STREET TO WEBER ROAD

DRAINAGE SCHEDULE - STRUCTURES (1 OF 2)

SCALE: 1" = 50'
DATE: 02/23/2007

DRAWN BY JPA
CHECKED BY TEH

FINAL