

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-3	WILL	305	206
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

WEBER ROAD NORTHBOUND ENTRANCE TO I-55

STAGE 2

LOCATION	UNSUITABLE EXCAVATION (CU YD)	EARTH EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
4909+59.25 TO 4915+00.00	90	990	90	840	-20	820

STAGE 2A

LOCATION	UNSUITABLE EXCAVATION (CU YD)	EARTH EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
4909+59.25 TO 4915+00.00	150	340	150	290	-95	195

WEBER ROAD SOUTHBOUND EXIT TO I-55

STAGE 1

LOCATION	UNSUITABLE EXCAVATION (CU YD)	EARTH EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
1903+00.00 TO 1906+00.00	205	20	205	15	-1995	-1980

STAGE 2

LOCATION	UNSUITABLE EXCAVATION (CU YD)	EARTH EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
1906+00.00 TO 1910+50.00	135	535	135	455	-15	440

STAGE 2A

LOCATION	UNSUITABLE EXCAVATION (CU YD)	EARTH EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
1906+00.00 TO 1910+50.00	80	120	80	100	-185	-85

WEBER ROAD NORTHBOUND EXIT TO I-55

STAGE 1

LOCATION	UNSUITABLE EXCAVATION (CU YD)	EARTH EXCAVATION (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
3898+19.21 TO 3902+57.20	215	55	215	45	-2,725	-2,680

NOTES:

- EXCAVATION TO BE USED AS EMBANKMENT ADJUSTED FOR 15% SHRINKAGE
- GRASS MEDIAN TOPSOIL AND VEGETATION SHALL BE REMOVED (ASSUMED 6 INCH DEPTH) AT THE CONTRACT UNIT PRICE FOR "REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL"
- OUTTER SIDESLOPE TOPSOIL AND VEGETATION SHALL BE REMOVED (ASSUMED 6 INCH DEPTH) AND 50% ASSUMED UNSUITABLE, PAID FOR AT THE CONTRACT UNIT PRICE FOR "REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL" AND 50% ASSUMED SUITABLE, PAID FOR AT THE CONTRACT UNIT PRICE FOR "TOPSOIL EXCAVATION AND PLACEMENT"
- VOLUMES ARE CALCULATED USING END AREAS SHOWN ON SHEETS 206A AND 206B. THESE END AREAS SUPERCEDE AREAS SHOWN ON CROSS SECTIONS.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 143RD STREET TO WEBER ROAD
 EARTHWORK SCHEDULE



SCALE:
 DATE: 02-23-07

DRAWN BY MGH
 CHECKED BY RMH

FINAL