

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2722	3061 (A,B,&C) RS	COOK	25	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100 % STATE				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16				
40600300	AGGREGATE (PRIME COAT)	TON	80	80				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	24	24				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2030	2030				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	487	487				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	472	472				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3046	3046				
42001300	PROTECTIVE COAT	SQ YD	221	221				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1371	1371				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	36266	36266				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	663	663				
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	1220	1220				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	815	815				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	156	156				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	249	249				
** 55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	7	7				
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	96	96				
60404940	FRAMES AND GRATES, TYPE 23	EACH	43	43				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3849	3849				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100 % STATE				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	545	545				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17792	17792				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2985	2985				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	290	290				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	735	735				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9178	9178				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	545	545				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17792	17792				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2985	2985				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	290	290				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	735	735				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	200	200				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	158	158				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	639	639				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	20				
70102625	TRAFFIC CONTROL AND PROTECTION STANDARD 701606	L SUM	1	1				
67100100	MOBILIZATION	L SUM	1	1				

NON PARTICIPATING

SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 17th Avenue  
 I.C. R.R. to 31st Street