

F.A. RTE. 290	SECTION 2006-030 I	COUNTY COOK	TOTAL SHEETS 78	SHEET NO. 3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		LOC. 1 I-90 016-0977 SFTY-2A	LOC. 2 ILL. 58 016-0980 SFTY-2A	LOC. 3 WOODFIELD 016-0978 SFTY-2A	I000
78100105	STONE RIPRAP CLASS A3	SQ YD	24		24		
44000415	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	10,645	9733	5609	1303	
X0325774	RELOCATE TEMPORARY IMPACT ATTENUATOR	EACH	6	3	3		
50102400	CONCRETE REMOVAL	CU YD	148	85	63		
50157300	PROTECTIVE SHIELD	SQ YD	9,875	5,600	3,510	765	
50300100	FLOOR DRAINS	EACH	20		20		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	218	119	90	9	
50300530	FLOOR DRAIN EXTENSION	EACH	8		8		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	47,020	25,690	19,530	1800	
59000200	EPOXY CRACK INJECTION	FOOT	352	211	137	4	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	726	726			
* 63000015	STEEL PLATE BEAM GUARD RAIL, TYPE D	FOOT	623			623	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	12			12	
63200725	STEEL PLATE BEAM GUARD RAIL REMOVAL, TYPE D	FOOT	2953	1070	683	1200	
63304805	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 6	EACH	12	6	6		
64200105	SHOULDER RUMBLE STRIP	FOOT	10600	4232	4108	2260	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	5	4	2	1
67100100	MOBILIZATION	L SUM	1	0.5	0.3	0.2	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		0.5	0.5	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	11	5	4	2	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	87392	43696	26218	17478	
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	62900	31450	18870	12580	
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	11210	5605	3363	2242	
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	510	255	193		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	63079	31540	18924	12615	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3737	2127	1610		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4450	2840	1610		
* 72100100	SIGN PANEL OVERLAY	SQ FT	640	320	320		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14,500			14,500	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	6439	3213	2696	530	
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING - LINE 5"	FOOT	16,100			16,100	
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	1588	714	674	200	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	172	80	68	24	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	6710			6710	
X0320887	POLYMER CONCRETE	CU FT	45		45		
X0321743	SILICONE JOINT SEALER, 1"	FOOT	1170	714	456		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N10	TON	1552	7	6	2	1537
40603600	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N10.5	TON	71				71
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	249	115	98	36	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	18,461				18,461
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	623				623

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		LOC. 1 I-90 016-0977 SFTY-2A	LOC. 2 ILL. 58 016-0980 SFTY-2A	LOC. 3 WOODFIELD 016-0978 SFTY-2A	I000
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	96		48	48	
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	10,645	9733	5609	1303	
X0322933	SILICONE JOINT SEALER, 2.5"	FOOT	239		239		
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	315		239	76	
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	590	516		74	
X0325201	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	2,356	941	913	502	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	980	597	290	93	
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	1753	1070	683		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.3	0.2	
X7012625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	EACH	1			1	
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1		1		
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	204	102	60	42	
Z0006202	BRIDGE DECK HYDRO-SCARIFICATION 3/4"	SQ YD	10,645	9733	5609	1303	
Z0015595	DECK DRAIN EXTENSIONS	EACH	86		60	26	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	45	30	10	5	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	441	255	91	95	
Z0065700	SLOPE WALL REPAIR	SQ YD	99		56	43	
X0325042	MODIFY EXISTING CONNECTION TO SIGN STRUCTURE	EACH	12	8	4		
Z0010605	CLEAN DRAINAGE SYSTEM	L SUM	1	1			
X0322469	PLUG EXISTING FLOOR DRAINS	EACH	12			12	

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

4/17/2007