

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES FED. 80% STATE 20%	ROADWAY IL.RTE.173		
				1000-2A	X071-2A	X071-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	393	393		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	112	112		
20200100	EARTH EXCAVATION	CU YD	1,691	1,691		
20101100	TREE TRUNK PROTECTION	EACH	22	22		
20101200	TREE ROOT PRUNING	EACH	22	22		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	895	895		
20300100	CHANNEL EXCAVATION	CU YD	691	691		
20400800	FURNISHED EXCAVATION	CU YD	3,145	3,145		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	241		107	134
20800150	TRENCH BACKFILL	CU YD	33	33		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,344	4,344		
25000300	SEEDING, CLASS 3	ACRE	0.7	0.7		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	75	75		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	75	75		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	75	75		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	3388	3388		
25200110	SODDING, SALT TOLERANT	SQ YD	956	956		
25200200	SUPPLEMENTAL WATERING	UNIT	26	26		
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	50	50		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	600	600		
28000700	MULCH, METHOD 1	ACRE	2	2		
28000720	MULCH, METHOD 2	ACRE	2	2		
28000300	TEMPORARY DITCH CHECKS	EACH	5	5		
28000400	PERIMETER EROSION BARRIER	FOOT	3,400	3,400		
28000500	INLET AND PIPE PROTECTION	EACH	4	4		
28000905	FENCE (EROSION CONTROL), SPECIAL	FOOT	3,400	3,400		
28100103	STONE RIPRAP, CLASS A2	SQ YD	1,206		489	717
28100105	STONE RIPRAP, CLASS A3	SQ YD	72	72		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1134		489	645
28200200	FILTER FABRIC	SQ YD	1192	72	489	631

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES FED. 80% STATE 20%	ROADWAY IL.RTE.173		
				1000-2A	X071-2A	X071-2A
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	823	823		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	84	84		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	36	36		
40600300	AGGREGATE (PRIME COAT)	TON	82	82		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600990	TEMPORARY RAMP	SQ YD	242	242		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	147	147		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1428	1428		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	10	10		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	140	140		
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SQ YD	418	418		
40701951	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/2"	SQ YD	4,469	4,469		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	540	540		
44000100	PAVEMENT REMOVAL	SQ YD	5,460	5,460		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	217	217		
44000700	APPROACH SLAB REMOVAL	SQ YD	216	216		
44004250	PAVED SHOULDER REMOVAL	SQ YD	2,089	2,089		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	186	186		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2087	2087		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1	
50200100	STRUCTURE EXCAVATION	CU YD	487		223	264
50202901	COFFERDAM (LOCATION - 1)	EACH	1		1	
50202902	COFFERDAM (LOCATION - 2)	EACH	1		1	
50202903	COFFERDAM (LOCATION - 3)	EACH	1		1	
50202904	COFFERDAM (LOCATION - 4)	EACH	1		1	
50202905	COFFERDAM (LOCATION - 5)	EACH	1			1
50202906	COFFERDAM (LOCATION - 6)	EACH	1			1
50202907	COFFERDAM (LOCATION - 7)	EACH	1			1
50202908	COFFERDAM (LOCATION - 8)	EACH	1			1

\* SPECIALTY ITEMS

Rev.



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
ILLINOIS ROUTE 173

SCALE: NONE  
DATE: APRIL 25, 2007

DRAWN BY: A.C.S.  
CHECKED BY: S.J.P.