

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES FED. 80% STATE 20%	ROADWAY	OVERFLOW	PISCASAW
				IL.RTE.173	BRIDGE STP FUNDS	BRIDGE FUNDS
				I000-2A	X071-2A	X071-2A
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10	10		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	24	24		
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	12	12		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,101	1,101		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	74	74		
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1		
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1		
* X0325752	AERIAL CABLE, 2-1/C NO. 2, ALUMINUM, WITH MESSENGER WIRE	FOOT	320	320		
* X0325753	AERIAL CABLE, 2-1/C NO. 4/0, ALUMINUM, WITH MESSENGER WIRE	FOOT	2,415	2,415		
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	30	30		
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	8	8		
* 83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	2	2		
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	8	8		
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	16	16		
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2	2		
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1		
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1		
XX003404	TEMPORARY PAVEMENT, 8"	SQ YD	992	992		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	43	43		
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	14	14		
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	2			2
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1		
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1			1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1	
X7030100	WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III	FOOT	2,396	2,396		
Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	6,238	6,238		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	8	8		
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	16	16		
⊙ Z0076600	TRAINEES	HOUR	2,000	2,000		
* X0325754	REPLACEMENT OF SENSORS FOR ROADWAY WEATHER INFORMATION SYSTEM	L SUM	1		0.5	0.5

⊙ Y080  
\* SPECIALTY ITEMS

**CR & A**  
**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
ILLINOIS ROUTE 173

SCALE: NONE  
DATE: APRIL 25, 2007

DRAWN BY: A.C.S.  
CHECKED BY: S.J.P.