

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	131B (1&2) BR	McHENRY	107	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PIPE UNDERDRAIN SCHEDULE

CONTRACT NO. 60883

STATION	CONCRETE HEADWALL (EACH)	CONCRETE HEADWALL LOCATION (LF/RT)	PIPE DRAIN 4" (FEET)	PIPE UNDERDRAIN 6" (FEET)	PIPE UNDERDRAIN (SPECIAL) 6" (FEET)
89+10	1	RT	0'	40'	9'
89+72	1	LF	15'		
89+72	1	RT	15'		
90+74	1	LF	15'		
90+74	1	RT	15'		
91+05	1	RT		40'	9'
94+00	1	RT		40'	9'
97+00	1	RT		40'	9'
98+56	1	RT	15'		
98+92	1	LF	15'		
100+77	1	RT	15'		
101+14	1	LF	15'		
101+50	1	RT		40'	10'
104+00	1	RT		40'	10'
TOTAL	14		120'	240'	56'

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
ILLINOIS ROUTE 173

CR & A
CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
1-312-372-2023 FAX: 1-312-372-5274

SCALE: NONE
DATE: APRIL 16, 2007
DRAWN BY: A.C.S.
CHECKED BY: S.J.P.