

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	102	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
* 99(1&2)AC-R-2		CONTRACT NO. 60B97		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	WILL COUNTY													
				ROADWAY WESTERN FRONTAGE ROAD	SIGNING	STRUCTURE CULVERT	CONSTRUCTION TYPE CODE										
				I000-2A	Y002-1C	Y007											
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	56	56													
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	71	71													
20101100	TREE TRUNK PROTECTION	EACH	4	4													
20200100	EARTH EXCAVATION	CU YD	7,235	7,235													
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	8554	8554													
20400800	FURNISHED EXCAVATION	CU YD	13,430	13,430													
20700220	POROUS GRANULAR EMBANKMENT	CU YD	23				23										
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	189	189													
20800150	TRENCH BACKFILL	CU YD	200	200													
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	3,244	3,244													
25000210	SEEDING, CLASS 2A	ACRE	6.00	6.00													
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	523	523													
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	523	523													
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	523	523													
25100630	EROSION CONTROL BLANKET	SQ YD	62,080	62,080													
25200110	SODDING, SALT TOLERANT	SQ YD	1,060	1,060													
25200200	SUPPLEMENTAL WATERING	UNIT	31.8	31.8													
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	25	25													
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	701	701													
28000300	TEMPORARY DITCH CHECKS	EACH	30	30													
28000400	PERIMETER EROSION BARRIER	FOOT	5,923	5,923													
28000500	INLET AND PIPE PROTECTION	EACH	6	6													
28000510	INLET FILTERS	EACH	16	16													
28001000	AGGREGATE (EROSION CONTROL)	TON	5	5													
28100107	STONE RIPRAP, CLASS A4	SQ YD	70	70													
28200200	FILTER FABRIC	SQ YD	70	70													
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1,935	1,935													
31102500	SUB-BASE GRANULAR MATERIAL, TYPE C 8"	SQ YD	4,488	4,488													
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	200	200													
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,285	1,285													
40600895	CONSTRUCTING TEST STRIP	EACH	2	2													
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5	5													
40701996	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 15 3/4"	SQ YD	12,852.0	12,852.0													

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI 55 WEST FRONTAGE ROAD AT IL 59
 SECTION: 99(1&2)AC-R-2

SUMMARY OF QUANTITIES I

SCALE: _____ DRAWN BY: JB
 DATE: 03/22/2007 CHECKED BY: ACL



TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 260 N. MICHIGAN AVE. CHICAGO, IL 60601
 TELEPHONE: 312.587.9000

S:\00029\06N...S\00029\06N...T\00029\06C.DGN
 3-22-2007 8:55:00
 T:\DOCUMENT\932730\06C.DGN\06C.DGN\06C.DGN
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

Rev.