

# SUMMARY OF QUANTITIES

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	102	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
991&21AC-R-2		CONTRACT NO. 60B97		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	WILL COUNTY																
				ROADWAY WESTERN FRONTAGE ROAD	SIGNING	STRUCTURE CULVERT	CONSTRUCTION TYPE CODE													
				1000-2A	1002-10	YDOT														
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	22	22																
42001300	<i>PROTECTIVE COAT</i>	<i>SQ YD</i>	<i>122</i>	<i>122</i>																
44000100	PAVEMENT REMOVAL	SQ YD	8,736	8,736																
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	658	658																
44004850	<i>PAVED SHOULDER REMOVAL</i>	<i>SQ YD</i>	<i>870</i>	<i>870</i>																
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	918	918																
48101500	<i>AGGREGATE SHOULDERS, TYPE B 6"</i>	<i>SQ YD</i>	<i>447</i>	<i>447</i>																
48203009	HOT-MIX ASPHALT SHOULDERS, 3"	SQ YD	141	141																
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	3,759	3,759																
50104300	CONCRETE HEADWALL REMOVAL	CU YD	1	1																
50105220	PIPE CULVERT REMOVAL	FOOT	44	44																
51205200	TEMPORARY SHEET PILING	SQ FT	<i>850</i>				<i>850</i>													
54003400	BOX CULVERT END SECTIONS, <i>SPECIAL</i>	EACH	2				2													
54020302	PRECAST CONCRETE BOX CULVERT 3' X 2' ( <i>M273</i> )	FOOT	74.5				74.5													
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	46	46																
54202137	PIPE CULVERTS, TYPE 3 RCCP 42"	FOOT	75	75																
54205062	<i>PIPE CULVERTS, SPECIAL 27"</i>	<i>FOOT</i>	<i>51</i>	<i>51</i>																
54207153	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	FOOT	193	193																
54207156	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 21"	FOOT	42	42																
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2																
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	4	4																
54214716	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 21"	EACH	2	2																
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	534	534																
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	8	8																
55100900	STORM SEWER REMOVAL 18"	FOOT	518	518																
55101800	STORM SEWER REMOVAL 42"	FOOT	46	46																
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE <i>B GRATE</i>	EACH	3	3																
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1																
60206805	CATCH BASINS, TYPE B, SPECIAL	EACH	1	1																
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1																
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1																
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1																
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1																
60500040	REMOVING MANHOLES	EACH	1	1																
60500050	REMOVING CATCH BASINS	EACH	2	2																

\* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI 55 WEST FRONTAGE ROAD AT IL 59  
SECTION: 991&21AC-R-2

## SUMMARY OF QUANTITIES II

SCALE: \_\_\_\_\_ DRAWN BY: JB  
DATE: 03/22/2007 CHECKED BY: ACL



TENGL & ASSOCIATES, INC.  
ENGINEERS ARCHITECTS PLANNERS  
200 N. MICHIGAN AVE. CHICAGO, IL 60601  
TELEPHONE: 312.636.6000

I:\S000029\HJDN...S000029\HJDN...ATTB002626.DGN  
 3-22-2007 8:59:01  
 I:\S000029\HJDN...S000029\HJDN...ATTB002626.DGN  
 3-22-2007 8:59:01  
 I:\S000029\HJDN...S000029\HJDN...ATTB002626.DGN  
 3-22-2007 8:59:01