

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	•	WILL	102	14
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
• 99(1&2)AC-R-2		CONTRACT NO. 60897		

55100900 STORM SEWER REMOVAL 18"				TOTAL	518
FROM STA.	TO STA.	OFFSET		FOOT	
18" RCCP	5017+83.73	5020+10.39	LT		226.65
18" RCCP	5020+10.39	5023+02.04	LT		291.66

55101800 STORM SEWER REMOVAL 42"				TOTAL	46
FROM STA.	TO STA.	OFFSET		FOOT	
42" RCCP	5023+02.04	5023+34.94	LT		46.47

51205200 TEMPORARY SHEET PILING			TOTAL	850
				SQ FT
STAGE II		595.00		
STAGE III		255.00		

60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12				TOTAL	192
				FOOT	
RIVER CROSSING DRIVE	EB	OUTSIDE		71.33	
RIVER CROSSING DRIVE		MEDIAN		95.27	
RIVER CROSSING DRIVE	WB	OUTSIDE		25.16	

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24				TOTAL	160
STA	STA	MEASURED LENGTH		FOOT	
WFR SB	5543+76.62	554455.00	83.92	76.92	
WFR NB	5543+73.28	554455.00	89.73	83.23	

63000000 STEEL PLATE BEAM GUARD RAIL, TYPE A			TOTAL	387.5
FROM STA.	TO STA.			FOOT
NB WEST FRONTAGE ROAD	5513+85.84	5517+73.34		387.50

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)				TOTAL	2
FROM STA.	TO STA.			EACH	
NB W. FRONTAGE RD	5513+35.84	5513+85.84		1.00	
NB W. FRONTAGE RD	5517+73.34	5518+23.34		1.00	

63500105 DELINEATORS							TOTAL	62
	FROM STA.	TO STA.	LENGTH	SPACING	# OF POSTS	# OF DEL. /POST		EACH
WFR SB CURVE	5500+00.00	5503+15.00	315.00	400.00	1.00	1.00	1.00	1.00
WFR SB TANGENT	5503+15.00	5516+09.00	1294.00	400.00	4.00	1.00	4.00	
WFR SB CURVE	5516+09.00	5523+19.00	710.00	100.00	12.00	1.00	12.00	
+ 4 POSTS FOR SP.								
WFR SB TANGENT	5523+19.00	5530+50.00	731.00	400.00	2.00	1.00	2.00	
WFR SB CURVE	5530+50.00	5537+79.00	729.00	100.00	12.00	2.00	12.00	
+ 4 POSTS FOR SP.								
WFR SB TANGENT	5537+79.00	5543+76.00	597.00	400.00	2.00	1.00	2.00	
WFR NB CURVE	5500+00.00	5503+15.00	315.00	400.00	1.00	1.00	1.00	
WFR NB TANGENT	5503+15.00	5513+01.82	986.82	400.00	3.00	1.00	3.00	
WFR NB CURVE	5518+56.26	5523+19.00	462.74	100.00	9.00	2.00	9.00	
+ 4 POSTS FOR SP.								
WFR NB TANGENT	5523+19.00	5530+50.00	731.00	400.00	2.00	1.00	2.00	
WFR NB CURVE	5530+50.00	5537+79.00	729.00	100.00	12.00	1.00	12.00	
+ 4 POSTS FOR SP.								
WFR NB TANGENT	5537+79.00	5543+76.00	597.00	400.00	2.00	2.00	2.00	

66500105 WOVEN WIRE FENCE, 4'			TOTAL	2368
FROM STA.	TO STA.			FOOT
WFR STAGE I	5003+54.81	5026+60.79		2308.31
WFR STAGE III ADD. REQUIRED	5519+42.42	TIE TO EXIST I-55		60.00

66502300 WOVEN WIRE FENCE REMOVAL				TOTAL	2306
FROM STA.	TO STA.			FOOT	
WFR STAGE I	5003+54.81	5026+60.79		2305.98	

66502400 WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED				TOTAL	2308
FROM STA.	TO STA.			FOOT	
WFR STAGE III	5496+64.06	5519+42.42		2278.36	
WFR STAGE III	5519+42.42	TIE TO EXIST I-55		30.00	

54205062 PIPE CULVERTS, SPECIAL 27"			TOTAL	51 FOOT
STA.				
STA. 5516+10.84	STAGE I	6'		
STA. 5516+10.84	STAGE II	45'		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 WEST FRONTAGE ROAD AT IL 59
SECTION: 99(1&2)AC-R-2

SCHEDULE OF QUANTITIES VI

SCALE: _____ DRAWN BY: JB
DATE: 3/22/2007 CHECKED BY: ACL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
305 N. MICHIGAN AVE. CHICAGO, IL 60610
TEL: 312.329.3000

\SC00078.dgn - AT 10:02:26 AM
 4-23-2007 10:02:26 AM
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63