

# SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	•	WILL	102	15
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
• 99(1&2)AC-R-2		CONTRACT NO. 60B97		

70301000 WORK ZONE PAVEMENT MARKING REMOVAL							TOTAL	1603
FROM STA.	TO STA.	THEO. LGT.	ACT. LGT.	WIDTH	MULT.	SQ FT		
STAGE II								
WFR SB AUX GORE	5496+61.81	5496+96.62	107.50	0.67	1.00	71.59		
WFR SB AUX GORE	5496+61.81	5496+96.62	39	1	1	39.00		
WFR CEN DOUB YEL	5003+52.55	5006+90.75	338.20	0.33	2.00	225.44		
WFR NB EDGE	5002+62.15	5025+22.82	2260.67	0.33	1.00	753.48		
WFR CEN DOUB YEL	5018+60.62	5025+22.82	662.20	0.33	2.00	441.03		
RCD LT MARKING						36.40		
RCD LT MARKING						36.40		

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS					TOTAL	171
FROM STA.	TO STA.				SQ FT	
WFR SB AUX	5496+96.62	5499+78.32	ONLY		22.90	
	5496+96.62	5499+78.32	(ARROW)		15.80	
	5496+96.62	5499+78.32	(ARROW)		15.80	
RIVER CROSSING DRIVE			ONLY		22.90	
			ONLY		22.90	
			(ARROW)		15.80	
			(ARROW)		15.80	
			ONLY		22.90	
			(ARROW)		15.80	

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"						TOTAL	18728
FROM STA.	TO STA.	DESCRIPTION	LENGTH	NUMBER	FOOT		
WFR CENTER	5496+61.81	5517+96.63	YELLOW SOLID DOUBLE	2134.82	2.0	4269.64	
WFR CENTER	5518+87.79	5544+03.28	YELLOW SOLID DOUBLE	2515.49	2.0	5030.98	
WFR NB	5495+71.40	5543+43.28	WHITE EDGE LINE	4771.88	1.00	4771.88	
WFR NB	5543+43.28	RADIUS RETURN	WHITE EDGE LINE	168.55	1.00	168.55	
WFR SB	5499+78.32	5517+74.11	WHITE EDGE LINE	1795.79	1.00	1795.79	
WFR SB	5517+74.11	RADIUS RETURN	WHITE EDGE LINE	41.43	1.00	41.43	
WFR SB	RADIUS RETURN	5519+27.55	WHITE EDGE LINE	75.42	1.00	75.42	
WFR SB	5519+27.55	5543+46.62	WHITE EDGE LINE	2419.07	1.00	2419.07	
WFR SB	5543+46.62	RADIUS RETURN	WHITE EDGE LINE	154.75	1.00	154.75	

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"								TOTAL	218
FROM STA.	TO STA.	DESCRIPTION	LENGTH	WIDTH	MULT	FOOT			
WFR SB AUX	5496+96.62	5498+46.68	WHITE LANE LINE	150.06	1.00	150.06			
WFR SB AUX	5498+46.68	5499+78.32	WHITE SKIP DASH	131.64	0.25	32.91			
RCD SB	LANE LINE		WHITE LANE LINE	35.40	1.00	35.40			

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"				TOTAL	107
FROM STA.	TO STA.			FOOT	
WFR SB AUX GORE	5496+61.81	5496+96.62		107.50	

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"					TOTAL	39
FROM STA.	TO STA.			FOOT		
WFR SB AUX GORE	5496+61.81	5496+96.62		39.00		

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"				TOTAL	38
STA				FOOT	
RCD				22.90	
WFR	554403.28			15.00	

78100100 RAISED REFLECTIVE PAVEMENT MARKER						TOTAL	166
FROM STA.	TO STA.	LENGTH	TYPE	SPACING #	CASINGS EACH		
WEST FRONTAGE RD	5496+61.80	5544+03.28	4741.48	TWO-WAY AMBERS	80.00	2.0	120.00
CURVES EXTRA	5500+00.00	5503+15.33	315.33	TWO-WAY AMBERS	80.00	2.0	8.00
CURVES EXTRA	5516+09.15	5523+19.50	710.35	TWO-WAY AMBERS	80.00	2.0	18.00
CURVES EXTRA	5530+05.84	5537+79.73	773.89	TWO-WAY AMBERS	80.00	2.0	20.00

78200410 GUARDRAIL MARKERS, TYPE A					TOTAL	6
FROM STA.	TO STA.	LENGTH	SPACING	EACH		
NB WEST FRONTAGE ROAD	5513+35.84	5518+22.47	486.63	80.00		6.08

I:\SC000275\EGAL\ATT000262.DGN  
 4-23-2007 10:52:4  
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63  
 BONDILLIO

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI 55 WEST FRONTAGE ROAD AT IL 59  
 SECTION: 99(1&2)AC-R-2

## SCHEDULE OF QUANTITIES VII

SCALE: \_\_\_\_\_ DRAWN BY: JB  
 DATE: 3/22/2007 CHECKED BY: ACL

**TENG**

TENG & ASSOCIATES INC.  
 ENGINEERS ARCHITECTS PLANNERS  
 305 N. MICHIGAN AVE. CHICAGO, IL 60610  
 TELEPHONE: 312.666.9900