

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1374	0406 WRS	COOK	43	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

**D-91-106-07**

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 ROADWAY	Y031-IF SIGNAL			
* XX00593A	REOPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL II	EACH	1		1			
20101100	TREE TRUNK PROTECTION	EACH	9	9				
20101200	TREE ROOT PRUNING	EACH	4	4				
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	2	2				
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	2	2				
20200100	EARTH EXCAVATION	CU YD	191	191				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	91	91				
20800150	TRENCH BACKFILL	CU YD	37.5	37.5				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	795	795				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10				
25200110	SODDING, SALT TOLERANT	SQ YD	795	795				
25200200	SUPPLEMENTAL WATERING	UNIT	8	8				
28000400	PERIMETER EROSION BARRIER	FOOT	1150	1150				
28000500	INLET AND PIPE PROTECTION	EACH	2	2				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	231	231				
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	231	231				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5				
40600300	AGGREGATE (PRIME COAT)	TON	25	25				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	4	4				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	419	419				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	114	114				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	28	28				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	536	536				
42001300	PROTECTIVE COAT	SQ YD	1124	1124				

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 ROADWAY	Y031-IF SIGNAL			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	44	44				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	294	294				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2658	2658				
42400800	DETECTABLE WARNINGS	SQ FT	36	36				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	5964	5964				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	388	388				
44000300	CURB REMOVAL	FOOT	152	152				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	934	934				
44000600	SIDEWALK REMOVAL	SQ FT	2384	2384				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	189	189				
44002222	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5 1/2"	SQ YD	91	91				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	57	57				
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	34	34				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4020	4020				
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				
550A0030	STORM SEWERS, CLASS A, TYPE 1 8"	FOOT	46	46				
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	70	70				
55100400	STORM SEWER REMOVAL 10"	FOOT	52	52				
60202505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	2	2				
60235200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	1	1				
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	1	1				
60260100	INLETS TO BE ADJUSTED	EACH	2	2				
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	2	2				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5				
60500050	REMOVING CATCH BASINS	EACH	2	2				

\* SPECIALTY ITEM  
 \*\* ~~NON PARTICIPATING ITEM~~

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 BELMONT AVENUE