

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1374	0406 WRS	COOK	43	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

D-91-106-07

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		I000 ROADWAY	Y031-IF SIGNAL					CODE NO	ITEM		UNIT	I000 ROADWAY	Y031-IF SIGNAL			
60600605	CONCRETE CURB, TYPE B	FOOT	135	135					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	76	76					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 12	FOOT	1011	1011					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	110	110					
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	7	7					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	60	60					
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1					* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1065		1065				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1					* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	6		6				
* 66900665	TCL SOIL ANALYSIS	EACH	1	1					* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	25		25				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	10		10				
67100100	MOBILIZATION	L SUM	1	1					* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	466		466				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1					* 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	14		14				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	223		223				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					* 81400100	HANDHOLE	EACH	7		7				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4					* 81400200	HEAVY-DUTY HANDHOLE	EACH	2		2				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2					* 81400300	DOUBLE HANDHOLE	EACH	1		1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	846	846					* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1210		1210				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	135.5	135.5					* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3107	3107					* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	438	438					* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	41	41					* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	496		496				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	76	76					* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	910		910				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	94	94					* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1280		1280				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	34.5		34.5				* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	592		592				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	135.5	135.5					* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1557		1557				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3107	3107					* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1		1				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	438	438														
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	41	41														

\* SPECIALTY ITEM  
\*\* NON-PARTICIPATING ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
BELMONT AVENUE

4/19/2007 08:38:13 AM C:\p100078\ssm\p100078.dgn