CONTRACT NO. 60C95

F.A. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
378	*	COOK	33	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

*(3738 & 3839) RS-3

SUMMARY OF QUANTITIES

PAY ITEM	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY 100% STATE	1000 McCORMICK BLVD	1000 TOUHY AVENUE
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	46	43	3
40600300	AGGREGATE (PRIME COAT)	TON	223	207	16
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	111.6	103.7	7.9
40600895	CONSTRUCTING TEST STRIP	EACH	3	2	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	647	548	99
40600990	TEMPORARY RAMP	SQ YD	431	365	66
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1,810	1,539	271
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX F_1 N90	TON	10,930	10,160	771
42001300	PROTECTIVE COAT	SQ YD	70	70	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	100		100
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	111,536	103,671	7,865
44000600	SIDEWALK REMOVAL	SQ FT	100		100
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400	300	100
44002208	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2"	SQ YD	16,161	13,740	2,421
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	5		5
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	204	150	54
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	315	200	115
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	13,650	11,700	1,950
55039700	STORM SEWERS TO BE CLEANED	FOOT	9,050	8,550	500
60250200	CATCH BASINS TO BE ADJUSTED	EACH	17	15	2
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	6	5	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	295	285	10
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	14	10	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	3	1
67100100	MOBILIZATION	L SUM	1	0.8	0.2
70102625	TRAFFIC CONTROL AND PROTECTION STANDARD 701606	L SUM	1	0.8	0.2
70102635	TRAFFIC CONTROL AND PROTECTION STANDARD 701701	L SUM	1	0.8	0.2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7606	7158	448
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1347	1092	255
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	56,954	54,159	2,795
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,164	4,150	1,014
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	104	104	
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,472	2,412	60
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	579	509	70
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,235	1,160	75
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,235	1,160	75
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,998	1,751	247
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	77	51	26
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4,392	4,082	310
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	377	347	30
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2693	2184	510
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	113,909	108,318	5,590
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	10,328	8,300	2,028
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	208	208	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4,944	4,824	120
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,158	1,018	140

*SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP 378 (McCORMICK BLVD.)
EMERSON ST./GOLF RD. TO DEVON AVE.

SCALE: NA DRAWN BY: EUB
DATE: 4/13/07 CHECKED BY: RJS

GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC.
CHICAGO, ILLINOIS

H:\Jobs2006\20063028-24\CAD\Site\dgn\00\SUMMARY OF QTYS24_v8.dg
04/11/2007 11:17:45 AM