F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	107RS-2	KANE	31	3
STA.		TO STA.		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

CONTRACT NO.: 62751

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	27,670	27,670		
40600300	AGGREGATE (PRIME COAT)	TON	180	180		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	145	145		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	955	955		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,125	2,125		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	669	669		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	168	168		
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	19,625	19,625		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	17,350	17,350		
42001300	PROTECTIVE COAT	SQ YD	7,315	7,315		
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	20,405	20,405		
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	18,440	18,440		
44000705	BARRIER MEDIAN REMOVAL	SQ FT	2,845	2,845		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3,455	3,455		
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	9,270	9,270		
44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SQ YD	1,335	1,335		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	5,105	5,105		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	2,020	2,020		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	3,510	3,510		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	119,370	119,370		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	75	75		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2,375	2,375		
60260100	INLETS TO BE ADJUSTED	EACH	11	11		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	9,270	9,270		
60619910	CONCRETE MEDIAN, TYPE SB-6.18	SQ FT	2,725	2,725		
60624600	CORRUGATED MEDIAN	SQ FT	4,990	4,990		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		

• SPECIALTY ITEM

SUMMARY OF QUANTITIES

	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000		
	70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1		
	70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1		
	70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70	70		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11,816	11,816		
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,248	1,248		
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	87,785	87,785		
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,895	6,895		
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	550	550		
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,246	1,246		
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	626	626		
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,900	3,900		
•	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,248	1,248		
•	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	87,785	87,785		
•	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6,895	6,895		
•	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	550	550		
•	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,246	1,246		
•	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	626	626		
•	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	958	958		
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	805	805		
	81400115	HANDHOLE TO BE ADJUSTED	EACH	3	3		
•	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,150	1,150		
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	216.7	216.7		
	X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	4,990	4,990		

• SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAU ROUTE 326 (IL 47)
GALENA BLVD TO SEAVEY RD

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE: March 23, 2007
DRAWN BY NEC
CHECKED BY SPF

3/23/2007 12:35:06 PM K:\IL82528\IL 47 - 3P\CADD\Design\825150D.dgn