


4/14/2007 2:46:55 PM k:\103528\1147 - 3p\cadd\design\103528\typical.dgn

4/14/2007 2:46:56 PM k:\103528\1147 - 3p\cadd\design\103528\typical.dgn

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	107RS-2	KANE	31	6
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		


CONTRACT NO.: 62751

- LEGEND**
- ① EXISTING CRC PAVEMENT, 8"
  - ①A EXISTING PCC PAVEMENT, 10"
  - ② EXISTING STABILIZED SUB-BASE (BAM), 4"
  - ③ EXISTING STABILIZED SHOULDER (BAM), 8"
  - ④ EXISTING GRANULAR MATERIAL, 4"
  - ⑤ EXISTING BITUMINOUS SURFACE, 3"
  - ⑥ PROPOSED POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90, 1 3/4"
  - ⑦ PROPOSED POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N90, 2 1/4"
  - ⑧ PROPOSED B-6.12 CURB AND GUTTER
  - ⑨ PROPOSED CONCRETE MEDIAN 4"
  - ⑩ PROPOSED AGGREGATE WEDGE SHOULDER, TYPE B
  - ⑪ EXISTING CURB AND GUTTER
  - ⑫ STRIP REFLECTIVE CRACK CONTROL TREATMENT
  - \* SEE MEDIAN DETAIL
  - \*\* LEVELING BINDER QUANTITIES INCLUDED IN THE PLANS ARE ESTIMATED FOR USE IN PREPARING THE EXISTING SHOULDERS FOR THE OVERLAY AND SHALL BE USED AS APPROVED BY THE ENGINEER. THE MINIMUM COMPACTED THICKNESS SHALL BE 3/4" AND THE MAXIMUM COMPACTED THICKNESS SHALL BE 2 1/4".




**PROPOSED TYPICAL SECTION - IL 47**

STA. 220+77 TO STA. 226+86  
 BRIDGE OMMISION STA. 226+85 TO STA. 229+83  
 STA. 229+83 TO STA. 238+75



**PROPOSED TYPICAL SECTION - IL 47**

STA. 45+38 TO STA. 168+00  
 SECTION WITH TURN LANES



**PROPOSED TYPICAL SECTION - IL 47**

STA. 45+38 TO STA. 168+00  
 NORMAL SECTION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAU ROUTE 326 (IL 47)  
 GALENA BLVD TO SEAVEY RD

**TYPICAL SECTIONS**

SCALE: VERT. DATE: Apr 11 03, 2007  
 HORIZ. DRAWN BY NEC  
 CHECKED BY SPF