

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
533	2004-117 RS	MCHENRY	26	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
20200100	EARTH EXCAVATION	CU YD	53	53				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	368	368				
20400800	FURNISHED EXCAVATION	CU YD	16	16				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	431	431				
25000210	SEEDING, CLASS 2A	ACRE	0.10	0.10				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10				
25100630	EROSION CONTROL BLANKET	SQ YD	431	431				
25200200	SUPPLEMENTAL WATERING	UNIT	6	6				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10				
28000300	TEMPORARY DITCH CHECKS	EACH	30	30				
28000400	PERIMETER EROSION BARRIER	FOOT	355	355				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	165	165				
35600704	HOT-MIX ASPHALT BASE COURSE WIDENING, 7"	SQ YD	240	240				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19				
40600300	AGGREGATE (PRIME COAT)	TON	95	95				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	262	262				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	35	35				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4010	4010				
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	47285	47285				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	200	200				
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	200	200				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1472	1472				
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	875	875				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	18	18				
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1	1				
63200310	GUARDRAIL REMOVAL	FOOT	875	875				
* 63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	18	18				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10300	10300				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	44210	44210				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	340	340				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	18	18				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18206	18206				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	44210	44210				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	340	340				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	18	18				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	273	273				
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	18				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	18	18				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3980	3980				

\* - SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 4/3/2007

4/3/2007