

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&I) WRS	WILL	334	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

100% STATE URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	PROP IL 59	EXIST IL 59	US 52	SIGNING	LIGHTING
				I000-2A	099-4642 X271-2A	099-0030 SFTY-2A	099-0139 SFTY-2A	Y002-1C	Y030-1E
XX002870	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	SQ YD	11102	11102					
XX003988	TEMPORARY CONCRETE BARRIER REMOVAL	FOOT	268	268					
XX005472	DRAINAGE STRUCTURE SPECIAL	EACH	4	4					
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	99436	99436					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5					
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1					
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	9	9					
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	6	6					
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	4	4					
Z0068400	STEEL CASINGS 42"	FOOT	40	40					
Z0076600	TRAINEES	HOUR	4000	4000					
35501288	HOT-MIX ASPHALT BASE COURSE, 2 1/2"	SQ YD	89656	89656					
X0325733	TEMPORARY ASPHALT WEDGE	SQ YD	2147	2147					
X0325741	REINFORCED CONCRETE PIPE ELBOW, SPAN 30 RISE 19	EACH	4	4					
X006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	7						7
X0325740	UNIT DUCT, 600V, 3-1/C NO. 2, 1/C NO. 4 GROUND, (EPR-TYPE RHW), 1 1/2" DIA. POLYETHYLENE	FOOT	1635						1635
X4421000	PARTIAL DEPTH PATCHING	TON	109	109					
X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	970	970					

0-1080
SPECIALTY ITEMS
URBAN, 90% FEDERAL, 10% STATE

PLOT DATE = 04/07/07
PLOT SCALE = AS SHOWN
USER NAME = RUSERS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (I-80 TO BLACK ROAD)
WIDENING AND RESURFACING

SUMMARY OF QUANTITIES
V

SCALE: N.T.S. DRAWN BY AG
DATE 03/22/07 CHECKED BY DDH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

Rev. 5-31-07