

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2946	3368 A-N	COOK	74	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT: 62915				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 1000-1A 90% FED 10% STATE	RETAINING WALL SFTY-2A 90% FED 10% STATE	TRAFFIC SIGNAL Y031-IF 90% FED 5% STATE 5% CALUMET CITY	NEW SIDEWALK SFTY-1B 50% STATE 50% CALUMET CITY		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2					
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2	2					
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	40	40					
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	270	270					
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	711	711					
550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	207	207					
550A2400	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 36"	FOOT	244	244					
55100500	STORM SEWER REMOVAL 12"	FOOT	547	547					
55100700	STORM SEWER REMOVAL 15"	FOOT	364	364					
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3					
60107600	PIPE UNDERDRAINS 4"	FOOT	600	600					
60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	6	6					
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1					
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60500040	REMOVING MANHOLES	EACH	2	2					
60500050	REMOVING CATCH BASINS	EACH	4	4					
60600605	CONCRETE CURB, TYPE B	FOOT	350	350					
60603300	GUTTER OUTLET	EACH	3	3					
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1733	1733					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	907	907					
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	110	110					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 1000-1A 90% FED 10% STATE	RETAINING WALL SFTY-2A 90% FED 10% STATE	TRAFFIC SIGNAL Y031-IF 90% FED 5% STATE 5% CALUMET CITY	NEW SIDEWALK SFTY-1B 50% STATE 50% CALUMET CITY		
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	150	150					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4150	4150					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	364	364					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15220	15220					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1643	1643					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	136	136					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	135	135					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	460	460					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	36					36	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	364	364					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15220	15220					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1643	1643					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	136	136					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	135	135					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	310	310					
* 78300100	PAVEMENT MARKING REMOVAL	SQ. FT.	160	160					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	233	233					

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
WENTWORTH AVE. AT RIVER OAKS DR.

Rev.