

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	(4MFT)R	WINNEBAGO	353	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	Y031-1F													Y031-3D	SFTY-1B	J 000				
			J 000		I 000		J 000		TRAFFIC SIGNALS													
			100% STATE		100% STATE		STATE 55.6% CITY 44.4%		10% CITY 90% STATE		10% CITY 90% STATE		6.6% CITY 93.4% STATE		10% CITY 90% STATE		10% CITY 90% STATE		10% CITY 90% STATE		CITY ADDITIONS	
			URBAN	CONCRETE PAVEMENT	BITUMINOUS PAVEMENT	RAISED	BI-D	HARRISON	PEOPLES - 23rd AVE	BLACKHAWK	18th AVE	15th AVE	BROADWAY	INTER - CONNECT	EMERGENCY VEHICLE PRE-EMPTION	100% CITY	100% CITY	100% CITY	95% CITY 5% STATE			
TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY					
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	148.50	148.5																		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	956.75	956.75																		
20200100	EARTH EXCAVATION	CU YD	25,270.00	25,270.0																		
20800150	TRENCH BACKFILL	CU YD	8,658.00	8,658.0																		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	13,246.00	13,246.0																		
* 25000115	SEEDING, CLASS 1B	ACRE	2.00	2.0																		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180.00	180.0																		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180.00	180.0																		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180.00	180.0																		
* 25100115	MULCH, METHOD 2	ACRE	2.75	2.75																		
* 25200110	SODDING, SALT TOLERANT	SQ YD	14,505.00	14,505.0																		
* 25200200	SUPPLEMENTAL WATERING	UNIT	400.00	400.0																		
* 25000350	SEEDING, CLASS 7	ACRE	2.75	2.75																		
28000400	PERIMETER EROSION BARRIER	FOOT	1,520.00	1,520.0																		
28000500	INLET AND PIPE PROTECTION	EACH	58.00	58.0																		
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	47,880.00	47,880.0																		
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	2,819.00	2,819.0																		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1,880.00	1,880.0																		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	4,342.00	4,342.0																		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10.50	6.1	4.4																	
40600300	AGGREGATE (PRIME COAT)	TON	25.20	6.3	18.9																	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N 50	TON	621.00		621.0																	
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	935.00		935.0																	
40600990	TEMPORARY RAMP	SQ YD	494.00	150.0	344.0																	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	854.00	854.0																		
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	39,035.50	38,875.0		160.5																
42001200	PAVEMENT FABRIC	SQ YD	600.00	600.0																		
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	3,724.00	3,724.0																		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	59,340.00	49,288.0											10,052.0							
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	1,007.00	1,007.0																		
42400800	DETECTABLE WARNINGS	SQ FT	440.00	440.0																		
44000100	PAVEMENT REMOVAL	SQ YD	33,759.00	33,759.0																		

*SPECIALTY ITEMS

PLOT DATE = Mon Apr 30 09:28:59 2007
 FILE NAME = P:\Users\jv\Documents\2007\G4450\Draw.dgn
 PLOT SIZE = 11x17
 USER NAME = jv