CONTRACT NO. 64450

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	(4MFT)R	WINNEBAGO	353	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	J 000 100% STATE CONCRETE PAVEMENT QUANTITY	I 000 100% STATE BITUMINOUS PAVEMENT QUANTITY	J 000 STATE 55.6% CITY 44.4% RAISED BI-DIRECTIONAL QUANTITY	Y031-1F 10% CITY 90% STATE TRAFFIC SIGNALS HARRISON QUANTITY	Y031-1F 10% CITY 90% STATE PEOPLES - 23rd AVE QUANTITY	Y031-1F 6.6% CITY 93.4% STATE BLACKHAWK QUANTITY	Y031-1F 10% CITY 90% STATE 18th AVE QUANTITY	Y031-1F 10% CITY 90% STATE 15th AVE QUANTITY	Y031-1F 10% CITY 90% STATE BROADWAY QUANTITY	Y031-1F 10% CITY 90% STATE INTER - CONNECT QUANTITY	Y031-3D 100% CITY EMERGENCY VEHICLE PRE-EMPTION QUANTITY	SFTY-1B CITY ADDITIONS 100% CITY SIDEWALK QUANTITY	J 000 CITY ADDITIONS 95% CITY 5% STATE MEDIAN SURFACE QUANTITY
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	11,088.00		11,088.0											
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,967.00	2,967.0												
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	12,574.00	12,574.0												
44000600	SIDEWALK REMOVAL	SQ FT	53,180.00	53,180.0												
44002805	ISLAND REMOVAL	SQ FT	901.00	901.0												
44213200	SAW CUTS	FOOT	1,576.00	1,576.0												
50102600	CONCRETE REMOVAL	EACH	1.00	1.0												
50800105	REINFORCEMENT BARS	POUND	203.00	203.0												
50901760	PIPE HANDRAIL	FOOT	319.00	319.0												
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	86.00	86.0												
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	106.00	106.0												
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	107.00	107.0												
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	740.00	740.0												
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	305.00	305.0												
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	44.00	44.0												
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	621.00	621.0												
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	689.00	689.0												
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	2,278.00	2,278.0												
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	719.00	719.0												
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	343.00	343.0												
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	1,247.00	1,247.0												
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	78.00	78.0												
550A2500	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 8"	FOOT	82.00	82.0												
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	412.00	412.0												
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	95.00	95.0												
550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	274.00	274.0												
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	604.00	604.0												
550A2600	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 36"	FOOT	76.00	76.0												
550A2630	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 54"	FOOT	87.0	87.0												
* 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	864.00	864.0												

*SPECIALTY ITEMS

PLOT DATE = Mon Apr 30 09:21:02 2007
FILE NAME = c:\projects\p21698\d169f8cvr.dgn
PLOT SCALE = 75.0000 ' / IN.
USER NAME = gremtpm