

SUMMARY OF QUANTITIES

CONTRACT NO. 64450

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	4MFTR	WINNEBAGO	353	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	PAY ITEM	UNIT	J 000		I 000	Y031-1F										Y031-3D	SFTY-1B	J 000
			100% STATE		100% STATE	STATE 55.6% CITY 44.4%	CITY 10% STATE 90%		CITY 10% STATE 90%	6.6% CITY 93.4% STATE	CITY 10% STATE 90%	CITY 10% STATE 90%	CITY 10% STATE 90%	CITY 10% STATE 90%	CITY 10% STATE 90%	100% CITY	100% CITY	95% CITY 5% STATE
			URBAN	CONCRETE PAVEMENT	BITUMINOUS PAVEMENT	RAISED DIRECTIONAL	BI-D	HARRISON	PEOPLES - 23rd AVE	BLACKHAWK	18th AVE	15th AVE	BROADWAY	INTER - CONNECT	EMERGENCY VEHICLE PRE-EMPTION	SIDEWALK	MEDIAN SURFACE	
			TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	
67100100	MOBILIZATION	L SUM	1.00	1.0														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1.00	1.0														
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.00	1.0														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.00	1.0														
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.00	1.0														
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	240.00	240.0														
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18.00	18.0														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	63.00	63.0														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46,196.00	46,196.0														
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	466.00	466.0														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	325.00	325.0														
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	983.00	983.0														
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	8,435.00	8,435.0														
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	1,281.00	1,281.0														
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	1,488.00	1,488.0														
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	448.00	448.0														
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	449.00	449.0														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10,089.00	10,089.0														
* 72000100	SIGN PANEL - TYPE 1	SQ FT	49.50					18.0	16.5		15.0							
* 72000200	SIGN PANEL - TYPE 2	SQ FT	95.80					19.5	19.5	37.3	19.5							
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	SQ FT	1,442.20	1,442.2														
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	18,412.00	18,412.0														
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	3,169.00	3,169.0														
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	3,738.00	3,738.0														
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	1,166.00	1,166.0														
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	1,027.00	1,027.0														
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	677.00	677.0														
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,124.00	1,124.0														
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	4.00					1.0	1.0	1.0	1.0							
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	35.00					5.0	5.0	3.0	3.0			19.0				
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	4.00					1.0	1.0	1.0				1.0				
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	4,326.00					1,722.0	1,211.0	845.0	548.0							
* 82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	15.00					4.0	4.0	3.0	4.0							

*SPECIALTY ITEMS

PLOT DATE = Mon Apr 28 09:21:00 2007
 PLOT SCALE = 75.0000
 USER NAME = grantym