

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	(4MFT)R	WINNEBAGO	353	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	J 000		I 000		J 000		Y031-1F							Y031-3D	SFTY-1B	J 000							
			100% STATE		100% STATE		STATE 55.6% CITY 44.4%		CITY 10% STATE 90%		CITY 10% STATE 90%		6.6% CITY STATE 93.4%		CITY 10% STATE 90%		CITY 10% STATE 90%		CITY 10% STATE 90%		CITY 10% STATE 90%		CITY ADDITIONS		
			URBAN		CONCRETE PAVEMENT		BITUMINOUS PAVEMENT		RAISED DIRECTIONAL BI-D		TRAFFIC SIGNALS							EMERGENCY VEHICLE PRE-EMPTION		100% CITY		100% CITY		95% CITY 5% STATE	
			TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	HARRISON	PEOPLES - 23rd AVE	BLACKHAWK	18th AVE	15th AVE	BROADWAY	INTER - CONNECT	EMERGENCY VEHICLE PRE-EMPTION	SIDEWALK	MEDIAN SURFACE					
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4.00						1.0	1.0	1.0	1.0													
89502380	REMOVE EXISTING HANDHOLE	EACH	8.00						3.0	2.0	2.0	1.0													
* A2000114	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	14.00	14.0																					
* A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10.00	10.0																					
* B2000562	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 4' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	15.00	15.0																					
* B2002716	TREE, MALUS ADIRONDACK (ADIRONDACK CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	15.00	15.0																					
* B2005214	TREE, MALUS SUTYZAM (SUGAR TYME CRAB APPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	15.00	15.0																					
* D2001772	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	15.00	15.0																					
Z0007550	BUILDING REMOVAL	EACH	18.00	18.0																					
Z0013300	CONCRETE REMOVAL (SPECIAL)	SQ YD	14.00	14.0																					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.00	1.0																					
Z0017100	DOWEL BARS	EACH	470.00	470.0																					
Z0022800	FENCE REMOVAL	FOOT	1,484.00	1,484.0																					
Z0024476	FLEXIBLE DELINEATOR MAINTENANCE	EACH	50.00	50.0																					
Z0024478	FLEXIBLE DELINEATORS	EACH	191.00	191.0																					
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	16,832.00	16,832.0																					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.00	1.0																					
Z0049800	RELOCATE EXISTING SURVEY MARKERS	EACH	145.00	145.0																					
Z0050900	REMOVE CONCRETE FOUNDATION	EACH	30.00						8.0	8.0	6.0	8.0													
Z0065752	SLOTTED DRAIN 12" WITH 6" SLOT	FOOT	232.00	232.0																					
XX001135	PAVEMENT PATCHING SPECIAL	SQ YD	4,007.00	4,007.0																					
XX001386	SANITARY SEWERS, PVC, 8"	FOOT	537.00	537.0																					
XX001900	STORM SEWERS, TYPE 2 8" (FIELD TILE REPLACEMENT)	FOOT	133.00	133.0																					
XX003000	CLASS SI CONCRETE STEPS	CU YD	63.00	63.0																					
XX003163	EMERGENCY VEHICLE PRIORITY SYSTEM	EACH	6.00												6.0										
XX003165	VIDEO CAMERA DETECTOR SYSTEM	EACH	6.00						1.0	1.0	1.0	1.0	1.0	1.0											
XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1.00	1.0																					
XX004353	WATERMAIN RELOCATION	L SUM	1.00	1.0																					
XX004921	PEDESTRIAN PUSH-BUTTON SPECIAL	EACH	28.00						8.0	8.0	4.0	8.0													
XX005063	CLASS B PATCHES	SQ YD	612.50	612.5																					

*SPECIALTY ITEMS

Plot Date = Mon Apr 30 09:21:01 2007
 Plot Name = C:\Users\jg56598\Documents\1000000000.dgn
 Plot Scale = 76.8000 / IN.
 User Name = jg56598