

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	(4MFT)R	WINNEBAGO	353	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	J 000													Y031-3D		SFTY-1B		J 000																					
			URBAN			100% STATE			STATE 55.6% CITY 44.4%			CITY 10% STATE 90%			CITY 10% STATE 90%			6.6% CITY 93.4% STATE			CITY 10% STATE 90%			CITY 10% STATE 90%			CITY 10% STATE 90%			CITY 10% STATE 90%			100% CITY			CITY ADDITIONS					
			CONCRETE PAVEMENT			BITUMINOUS PAVEMENT			RAISED DIRECTIONAL BI-D			HARRISON			PEOPLES - 23rd AVE			BLACKHAWK			18th AVE			15th AVE			BROADWAY			INTER - CONNECT			EMERGENCY VEHICLE PRE-EMPTION			SIDEWALK			MEDIAN SURFACE		
			TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY					
XX006253	SANITARY MANHOLE, 4'-DIAMETER	EACH	3.00	3.0																																					
X0300351	CONCRETE STEP REMOVAL	EACH	6.00	6.0																																					
X0320239	CONCRETE WALL REMOVAL	FOOT	951.00	951.0																																					
X0320374	PLUG EXISTING SANITARY SEWERS	EACH	17.00	17.0																																					
X0320591	SANITARY MANHOLES TO BE REMOVED	EACH	9.00	9.0																																					
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	24.00	24.0																																					
X0321760	DOUBLE HANDHOLE REMOVAL	EACH	5.00						2.0	1.0	1.0	1.0																													
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	79.00	79.0																																					
X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	89.00	89.0																																					
X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	66.00	66.0																																					
X0322089	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	1991.00	1991.0																																					
X0322127	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	FOOT	541.00	541.0																																					
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	4,748.00	4,748.0																																					
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	1,693.00						562.0	426.0	278.0	427.0																													
X0323760	SANITARY SEWER SERVICE, 6" PVC, COMPLETE	EACH	3.00	3.0																																					
X0324652	TRACER CABLE	FOOT	5,794.00																																						
X0324886	CONDUIT INSTALLED, 1 1/4" DIA., NON-METALLIC	FOOT	35.00						14.0	6.0	6.0	9.0																													
X0324887	CONDUIT INSTALLED, 2 1/2" DIA., NON-METALLIC	FOOT	11,207.00						42.0	106.0	113.0	46.0	130.0	49.0	10,721.0																										
X0324888	CONDUIT INSTALLED, 4" DIA., NON-METALLIC	FOOT	1,819.00						478.0	233.0	191.0	300.0	337.0	280.0																											
X0324894	WATERMAIN MANHOLES TO BE ADJUSTED	EACH	20.00	20.0																																					
X0325055	CONCRETE MEDIAN SURFACE, (STAMPING)	SQ FT	15,886.00																																15,886.0						
X0325405	FILL EXISTING STORM SEWERS	CU YD	1,313.00	1,313.0																																					
X0712400	TEMPORARY PAVEMENT	SQ YD	588.00	588.0																																					
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	588.00	588.0																																					
X5011100	FOUNDATION REMOVAL	EACH	6.00	6.0																																					
X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	1,067.00	1,067.0																																					
X7800600	URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL	SQ FT	530.50																																530.5						

*SPECIALTY ITEMS

PLOT DATE = Mon Apr 30 09:21:01 2007
 FILE NAME = c:\p\projects\62165918\dl65918.dgn
 PLOT SCALE = 75.0000 / IN.
 USER NAME = gromtgm