

F.A.P. RYE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	(4MFT)R	WINNEBAGO	353	30
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SCHEDULE OF QUANTITIES

## X0321556 SANITARY MANHOLES TO BE ADJUSTED

EACH	LOCATION	OFFSET
	IL 251	
1.0	365 + 70	12.2' RT
1.0	368 + 57	12.8' RT
1.0	371 + 68	12.6' RT
1.0	373 + 03	12.5' RT
1.0	376 + 85	12.5' RT
1.0	380 + 78	9' RT
1.0	386 + 27	4.5' RT
1.0	386 + 69	4.5' RT
1.0	388 + 24	4.5' RT
1.0	390 + 54	1' RT
1.0	391 + 46	36' LT
1.0	392 + 08	5.5' LT
1.0	394 + 14	5.5' LT
1.0	395 + 51	5.7' LT
1.0	396 + 05	6.3' LT
1.0	398 + 75	6.8' LT
1.0	399 + 95	5.6' LT
1.0	403 + 91	3' RT
1.0	407 + 87	4' RT
1.0	411 + 13	4' RT
1.0	412 + 20	4' RT
1.0	413 + 17	4' RT
1.0	23RD AVE	
	164 + 12	1' RT
1.0	PEOPLES AVE	
1.0	158 + 20	13.5' LT
24.0	TOTAL	

## X0325405 FILL EXISTING STORM SEWERS

CU YD	LOCATION	OFFSET
	12" STORM SEWER	SIZE TO BE VERIFIED IN THE FIELD
1.89	360 + 38.60 - 359 + 88.70	LT
1.25	363 + 07.00 - 363 + 08.80	LT/RT
0.67	363 + 09.30 - 363 + 08.80	RT
0.73	365 + 94.80 - 365 + 86.30	LT/RT
0.70	365 + 93.60 - 365 + 86.30	RT
0.55	369 + 48.80 - 369 + 47.80	LT
0.52	369 + 47.80 - 369 + 45.22	LT/RT
0.64	369 + 48.10 - 369 + 45.22	RT
0.73	371 + 55.10 - 371 + 80.00	RT
9.86		23RD AVE
0.26	371 + 80.00 - 371 + 84.50	RT
1.02	371 + 84.50 - 371 + 82.80	RT
0.67	372 + 03.20 - 371 + 84.50	RT
1.43	373 + 06.60 - 372 + 72.30	LT
0.67	376 + 06.20 - 376 + 10.90	RT
0.49	376 + 14.10 - 376 + 10.90	LT
1.45	376 + 50.40 - 376 + 10.90	RT
0.73	379 + 06.20 - 379 + 03.00	RT
0.47	379 + 03.00 - 379 + 03.00	LT/RT
0.70	380 + 37.70 - 380 + 33.50	RT
0.49	380 + 37.70 - 380 + 33.50	LT/RT
1.51	382 + 20.50 - 381 + 94.30	RT
0.93	382 + 17.50 - 381 + 94.30	LT
0.70	382 + 70.00 - 382 + 63.40	RT/LT
0.67	382 + 77.90 - 382 + 63.30	LT
0.70	388 + 46.80 - 388 + 28.10	LT
0.90	388 + 46.80 - 388 + 28.30	RT/LT
0.73	392 + 38.50 - 352 + 34.60	RT/LT
0.47	392 + 37.70 - 392 + 34.60	LT
0.70	399 + 55.70 - 399 + 50.20	RT/LT
0.55	399 + 56.00 - 399 + 50.20	LT
0.93	401 + 23.60 - 401 + 19.60	RT/LT
0.47	401 + 25.00 - 401 + 19.60	LT
1.13	402 + 80.50 - 402 + 80.23	RT/LT
0.55	402 + 82.20 - 402 + 80.23	LT
1.09	404 + 45.40 - 404 + 09.80	RT
0.90	404 + 09.80 - 404 + 09.80	RT/LT
0.73	404 + 19.50 - 404 + 09.80	LT
0.44	404 + 34.90 - 404 + 19.50	LT
	21ST AVE	
0.67	100 + 40.00 - 100 + 40.00	LT/RT
	17TH AVE	
2.24	40 + 59.70 - 40 + 00.00	LT
42.92	SUBTOTAL	
	15" STORM SEWER	SIZE TO BE VERIFIED IN THE FIELD
7.14		PEOPLES AVE
0.27	372 + 66.80 - 372 + 71.40	LT
2.14	386 + 52.00 - 386 + 67.50	LT
	BLACKHAWK PARK	
5.14	88 + 36.30 - 89 + 48.90	LT/RT
	18TH AVE	
7.45	54 + 16.00 - 55 + 80.00	RT
7.27	55 + 80.00 - 57 + 40.80	RT
4.82	57 + 40.80 - 58 + 47.00	RT
	16TH AVE	
4.55	30 + 94.80 - 30 + 00.00	RT
38.77	SUBTOTAL	
	18" STORM SEWER	SIZE TO BE VERIFIED IN THE FIELD
1.83	360 + 40.00 - 360 + 13.33	RT
6.61	360 + 13.33 - 359 + 88.70	RT
22.65	396 + 03.84 - 399 + 50.00	LT
3.93	399 + 50.00 - 400 + 10.50	LT
7.13	400 + 10.50 - 401 + 19.50	LT
10.54	401 + 19.50 - 402 + 80.20	LT
6.15	402 + 80.20 - 403 + 74.20	LT
2.29	403 + 74.20 - 404 + 09.37	LT
	22ND AVE	
3.14	120 + 81.70 - 120 + 34.10	LT
	18TH AVE	
8.84	58 + 47.00 - 59 + 84.00	RT
1.64	63 + 50.00 - 63 + 50.00	LT/RT
74.7	SUBTOTAL	
	21" STORM SEWER	SIZE TO BE VERIFIED IN THE FIELD
32.87	392 + 34.55 - 396 + 03.84	LT
32.87	SUBTOTAL	
	24" STORM SEWER	SIZE TO BE VERIFIED IN THE FIELD
	21ST AVE	
6.98	100 + 39.10 - 101 + 00.00	RT
	20TH AVE	
11.98	70 + 98.00 - 70 + 00.00	LT
18.97	SUBTOTAL	

XX006253	SANITARY MANHOLE, 4'-DIAMETER	OFFSET
EACH	LOCATION	
	IL 251	
1.0	359 + 24	18.5' RT
1.0	364 + 00	43' RT
	HARRISON AVE	
1.0	9 + 76	67' RT
3.0	TOTAL	

X0300351	CONCRETE STEP REMOVAL	NO. OF STEPS	WIDTH	TOTAL DEPTH
EACH	LOCATION			
	IL 251			
1.0	381 + 75	LT	8	6ø11" + 2ø48" = 162"
1.0	383 + 16	LT	4	4ø12.5" + 1ø90" = 140"
1.0	401 + 78	RT	7	3ø11" = 33"
1.0	402 + 25	RT	4	4ø11" = 44"
1.0	402 + 75	RT	5	5ø10" = 50"
1.0	403 + 23	RT	4	4ø11" = 44"
6.0	TOTAL			

X0320239	CONCRETE WALL REMOVAL	OFFSET
EQOI	LOCATION	
	IL 251	
422.0	360 + 11	LT
116.0	364 + 26	LT
67.0	361 + 91	RT
67.0	381 + 47	LT
59.0	381 + 87	LT
116.0	382 + 78	LT
	HARRISON AVE	
41.0	7 + 61	LT
63.0	8 + 40	LT
951.0	TOTAL	

X0323760	SANITARY SEWER SERVICE, 6" PVC, COMPLETE	OFFSET
EACH	LOCATION	
	IL 251	
1.0	361 + 14	44' RT
1.0	362 + 35	40' RT
1.0	364 + 93	40' RT
3.0	TOTAL	

X0322923	SEGMENTAL CONCRETE BLOCK WALL	OFFSET
SO FT	LOCATION	
	IL 251	
671.27	357+63.67	RT
1409.71	359+32.19	LT
247.08	371+31.97	LT
134.55	373+28.92	LT
180.99	379+22.62	LT
262.51	381+47.01	LT
379.97	382+55.00	LT
187.53	386+83.43	LT
318.45	387+71.90	LT
145.89	390+26.94	RT
125.98	390+75.00	RT
213.85	391+19.62	RT
9.08	392+88.05	RT
86.93	392+97.43	RT
76.78	401+81.28	RT
162.26	402+10.78	RT
38.42	402+69.33	RT
71.75	402+93.70	RT
25.0	18TH AVE	
4,748.01	TOTAL	

X0320374	PLUG EXISTING SANITARY SEWERS	OFFSET
EACH	LOCATION	
	IL 251	
1.0	359 + 12	20' RT
1.0	360 + 09	34' RT
1.0	360 + 11	29.5' RT
1.0	360 + 13	32' RT
1.0	360 + 08	18' LT
1.0	360 + 10	15' LT
1.0	360 + 12	17' LT
1.0	362 + 00	32.6' RT
1.0	362 + 02	32.6' RT
1.0	362 + 53	17' LT
1.0	362 + 55	19' LT
1.0	362 + 57	17' LT
1.0	363 + 88	33' RT
1.0	364 + 75	17' RT
	HARRISON AVE	
1.0	9 + 57	10.7' RT
1.0	9 + 57	15.4' RT
1.0	9 + 76	64.3' RT
17.0	TOTAL	

X0324894	WATERMAIN MANHOLES TO BE ADJUSTED	OFFSET
EACH	LOCATION	
	IL 251	
1.0	363 + 18	21.3' RT
1.0	366 + 79	24' RT
1.0	368 + 24	24' RT
1.0	369 + 42	16' RT
1.0	373 + 00	16' RT
1.0	373 + 15	17' RT
1.0	376 + 93	38' RT
1.0	377 + 14	23' RT
1.0	382 + 24	12' RT
1.0	386 + 10	44' LT
1.0	386 + 45	16' RT
1.0	387 + 75	14' RT
1.0	388 + 42	34' LT
1.0	394 + 45	3' RT
1.0	396 + 15	25' RT
1.0	396 + 39	9' RT
1.0	400 + 05	8' RT
1.0	403 + 94	60' LT
1.0	404 + 00	29' RT
1.0	412 + 68	34' RT
20.0	TOTAL	

X0320591	SANITARY MANHOLES TO BE REMOVED	OFFSET
EACH	LOCATION	
	IL 251	
1.0	359 + 10	18.5' RT
1.0	360 + 11	32.4' RT
1.0	360 + 10	17.3' LT
1.0	362 + 01	32.6' RT
1.0	362 + 55	16.8' LT
1.0	363 + 90	33' RT
1.0	364 + 77	17' RT
	HARRISON AVE	
1.0	9 + 57	13' RT
1.0	9 + 76	67' RT
9.0	TOTAL	

PLOT DATE = Thu, May 17, 2007 9:07  
 FILE NAME = c:\pco\pco154\21556\0321556.dgn  
 PLOT SCALE = 1/8" = 1'-0"  
 USER NAME = grantpm