

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	(4MFT)R	WINNEBAGO	353	31
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

X0325405 FILL EXISTING STORM SEWERS

CU YD	LOCATION	OFFSET	SIZE TO BE VERIFIED IN THE FIELD
8.18	30" STORM SEWER 396 + 20.40 - 396 + 03.80	LT	
56.36	18TH AVE 63 + 42.00 - 60 + 34.00	LT	
64.54	SUBTOTAL		
34.54	33" STORM SEWER 386 + 67.50 - 388 + 28.12	LT	
89.31	388 + 28.12 - 392 + 34.55	LT	
123.85	SUBTOTAL		
106.03	36" STORM SEWER 382 + 63.26 - 386 + 67.50	LT	
106.03	SUBTOTAL		
113.32	42" STORM SEWER 360 + 00.00 - 363 + 08.80	LT/RT	
98.71	363 + 08.80 - 365 + 85.80	RT	
128.28	365 + 85.80 - 369 + 45.22	RT	
84.81	369 + 45.22 - 371 + 82.80	RT	
152.51	371 + 82.80 - 376 + 10.85	RT	
104.05	376 + 10.85 - 379 + 03.00	RT	
46.68	379 + 03.00 - 380 + 33.40	RT	
57.37	380 + 33.40 - 381 + 94.30	RT/LT	
24.59	381 + 94.30 - 382 + 63.26	LT	
810.31	SUBTOTAL		
1313.00	GRAND TOTAL		

X7800600 URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL

SQ.FI	LOCATION	OFFSET
	IL 251	
15.6	376 + 01	LT TURN ARROW
15.6	379 + 28	LT TURN ARROW
15.6	379 + 40	LT TURN ARROW
15.6	380 + 07	LT TURN ARROW
15.6	380 + 19	LT TURN ARROW
15.6	380 + 88	LT TURN ARROW
15.6	381 + 00	LT TURN ARROW
15.6	381 + 68	LT TURN ARROW
15.6	381 + 80	LT TURN ARROW
15.6	390 + 78	LT TURN ARROW
15.6	390 + 91	LT TURN ARROW
15.6	391 + 58	LT TURN ARROW
15.6	391 + 71	LT TURN ARROW
15.6	392 + 39	LT TURN ARROW
15.6	392 + 51	LT TURN ARROW
15.6	398 + 48	LT TURN ARROW
15.6	398 + 61	LT TURN ARROW
15.6	399 + 28	LT TURN ARROW
15.6	399 + 41	LT TURN ARROW
530.4	TOTAL	

X5011100 FOUNDATION REMOVAL

EACH	LOCATION	OFFSET	OLD SIGN or LIGHT FOUNDATION
	IL 251		
1	366 + 94	30' LT	OLD SIGN or LIGHT FOUNDATION
1	381 + 05	38.2' RT	OLD SIGN or LIGHT FOUNDATION
1	381 + 46	37' RT	OLD SIGN or LIGHT FOUNDATION
1	398 + 50	45' LT	OLD SIGN or LIGHT FOUNDATION
1	398 + 65	45' LT	OLD SIGN or LIGHT FOUNDATION
1	399 + 00	45' LT	OLD SIGN or LIGHT FOUNDATION
6.0	TOTAL		

X0325055 CONCRETE MEDIAN SURFACE (STAMPING)

SQ.FI	LOCATION	OFFSET
	IL 251	
5295.1	364 + 56.30 - 369 + 37.67	6' RT/LT
1656.1	374 + 61.45 - 376 + 12.00	6' RT/LT
3810.9	378 + 53.55 - 382 + 00.00	6' RT/LT
3631.1	390 + 03.40 - 393 + 33.50	6' RT/LT
1492.2	398 + 23.60 - 399 + 59.25	6' RT/LT
15,885.3	TOTAL	

X6640200 TEMPORARY CHAIN LINK FENCE

EQOI	LOCATION	OFFSET	REQUIREMENTS
50.0	7 + 53 - 8 + 35	LT	NW HARRISON 34' GATE REQUIRED
562.0	8 + 35 - 365 + 35	LT	34' & 12' GATE REQUIRED
60.0	362 + 50 - 363 + 11	RT	30' GATE REQUIRED
120.0	367 + 45 - 368 + 57	LT	SIGHT SCREEN REQUIRED 20' GATE REQUIRED
75.0	374 + 60 - 375 + 32	LT	SIGHT SCREEN REQUIRED 34' GATE REQUIRED
75.0	377 + 25 - 377 + 85	LT	SIGHT SCREEN REQUIRED
	23RD AVE		
125.0	163 + 37 - 165 + 00	RT	34' GATE REQUIRED
1,067.0	TOTAL		

X7800600 URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL

SQ.FI	LOCATION	OFFSET
	IL 251	
15.6	364 + 84	LT TURN ARROW
15.6	364 + 96	LT TURN ARROW
15.6	365 + 64	LT TURN ARROW
15.6	365 + 77	LT TURN ARROW
15.6	366 + 44	LT TURN ARROW
15.6	366 + 57	LT TURN ARROW
15.6	367 + 24	LT TURN ARROW
15.6	367 + 37	LT TURN ARROW
15.6	368 + 03	LT TURN ARROW
15.6	368 + 16	LT TURN ARROW
15.6	368 + 83	LT TURN ARROW
15.6	368 + 96	LT TURN ARROW
15.6	375 + 09	LT TURN ARROW
15.6	375 + 22	LT TURN ARROW
15.6	375 + 89	LT TURN ARROW

PLOT DATE : Thu May 17 07:38:23 2007
 FILE NAME : c:\projects\1159\1159.dwg
 USER NAME : graham