

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	14MFT/R	WINNEBAGO	353	34
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

EARTHWORK SCHEDULE

EARTH WORK SCHEDULE					
LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ SHRINK 25% EARTH	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)	TOP SOIL FURNISH & PLACE 4"
	CU YD	CU YD	CU YD	CU YD	SQ YD
	STAGE 1				
380+75 - 383+00	97	72	0	72	
383+00 - 389+00	1127	845	0	845	
389+00 - 392+00	230	172	0	172	
STAGE 2					
359+75 - 365+00	1319	989	0	989	355
365+00 - 371+00	1170	877	0	877	625
371+00 - 377+00	1308	981	0	981	304
377+00 - 383+00	1136	852	15	837	584
383+00 - 389+00	1033	775	11	764	499
389+00 - 390+25	301	226	0	226	117
STAGE 3					
388+75 - 389+00	4	3	0	3	
389+00 - 390+25	51	39	0	39	
STAGE 4					
358+00 - 365+00	1441	1081	0	1081	720
365+00 - 371+00	1405	1054	0	1054	909
371+00 - 377+00	1329	997	0	997	286
377+00 - 383+00	980	735	2	733	324
383+00 - 389+00	135	101	502	-400	939
389+00 - 391+00	223	167	4	164	148
STAGE 6					
390+25 - 395+00	1158	869	0	869	712
395+00 - 401+00	1279	959	0	959	570
401+00 - 405+50	1374	1031	0	1031	320
STAGE 7					
391+00 - 395+00	614	460	0	460	154
395+00 - 401+00	853	640	1	638	456
401+00 - 405+50	1536	1152	0	1152	368

EARTH WORK SCHEDULE					
LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ SHRINK 25% EARTH	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)	TOP SOIL FURNISH & PLACE 4"
	CU YD	CU YD	CU YD	CU YD	SQ YD
	SIDEROADS				
HARRISON AVE					
7+25 - 9+25	268	201	0	201	89
PEOPLES/23RD AVE					
157+79 - 159+25	608	456	0	456	153
160+75 - 164+50	1289	966	29	937	1705
22ND AVE (EB)					
120+50 - 120+95	108	81	0	81	82
22ND AVE (WB)					
110+50 - 111+54	127	96	0	96	145
21ST AVE					
100+50 - 101+64	254	191	0	191	232
BLACKHAWK PARK AVE					
88+13 - 89+25	291	218	0	218	214
20TH AVE					
70+25 - 71+61	328	246	0	246	360
18TH AVE					
58+25 - 59+25	211	159		159	
60+25 - 63+75	761	570	18	552	1116
17TH AVE					
40+25 - 41+40	234	176	0	176	192
16TH AVE					
28+25 - 29+50	218	163	0	163	259
30+25 - 31+73	467	350	0	350	309
TOTAL	25,266	18,950	582	18,368	13,246

PLOT DATE = Fri Apr 27 10:55:41 2007
 FILE NAME = c:\projects\21898\dwg\earthwork.dgn
 USER NAME = gromppm