

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	44MTR	WINNEBAGO	353	236
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# TRAFFIC SIGNAL QUANTITIES

PAY CODE	ITEM	UNIT	HARRISON QUANTITY	PEOPLE-23rd AVE TOTAL	BLACKHAWK TOTAL	18th AVE TOTAL	15th AVE TOTAL	BROADWAY TOTAL	INTERCONNECT TOTAL	TOTALS
72000100	SIGN PANEL - TYPE 1	SQ FT	18	16.5		15				49.5
72000200	SIGN PANEL - TYPE 2	SQ FT	19.5	19.5	37.25	19.5				95.75
80500100	SERVICE INSTALLATION, TYPE A	EACH	1	1	1	1				4
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5	5	3	3			19	35
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1	1	1			1		4
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) I/C No 10	FOOT	1722	1211	845	548				4326
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	4	4	3	4				15
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1	1	1	1				4
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1	1	1				4
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	1694	1346	386	911				4337
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1750	1402	407	953				4512
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	2718	1460	777	1518				6473
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	2962	776	564	1239				5541
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO 6 3C	FOOT	34	26	26	29				115
87502420	TRAFFIC SIGNAL POST GALVANIZED STEEL 8 FT	EACH		3						3
87502490	TRAFFIC SIGNAL POST GALVANIZED STEEL 15 FT	EACH			1					1
87502500	TRAFFIC SIGNAL POST GALVANIZED STEEL 16 FT	EACH	4							4
87702850	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT	EACH			1					1
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT	EACH			1					1
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT	EACH		1						1
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT	EACH		0		1				1
87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT	EACH		2		2				4
87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT	EACH		1						1
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT	EACH	1		1					2
87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT	EACH	1			1				2
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT	EACH	2							2
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6	9	3					18

PLOT DATE = Thu May 17 08:08:52 2007  
 FILE NAME = G:\projects\021818\021818.dwg  
 USER NAME = ggrant