

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	(4MFT)R	WINNEBAGO	353	237
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# TRAFFIC SIGNAL QUANTITIES

PAY CODE	ITEM	UNIT	HARRISON QUANTITY	PEOPLE-23rd AVE TOTAL	BLACKHAWK TOTAL	18th AVE TOTAL	15th AVE TOTAL	BROADWAY TOTAL	INTERCONNECT TOTAL	TOTALS
87800400	CONCRETE FOUNDATION, TYPE E, 30 INCH	FOOT			10					10
87800415	CONCRETE FOUNDATION, TYPE E, 36 INCH	FOOT	60	54	26	54				194
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3	3	3	3				12
87900200	DRILL EXISTING HANDHOLE	EACH	5				11	11		27
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2							2
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8	8	6	8				30
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	6	2	2	3				13
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	6	2	2	3				13
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED, WITH COUNT-DOWN TIMER	EACH	8	8	4	8				28
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	14	10	8	11				43
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1							1
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH					1	1		2
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1	1	1				4
89502380	REMOVE EXISTING HANDHOLE	EACH	3	2	2	1				8
X0321760	DOUBLE HANDHOLE REMOVAL	EACH	2	1	1	1				5
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	562	426	278	427				1693
X0324652	TRACER CABLE	FOOT							5794	5794
X0324886	CONDUIT INSTALLED, 1 1/4" DIA., NON-METALLIC	FOOT	14	6	6	9				35
X0324887	CONDUIT INSTALLED, 2 1/2" DIA., NON-METALLIC	FOOT	42	106	113	46	130	49	10721	11207
X0324888	CONDUIT INSTALLED, 4" DIA., NON-METALLIC	FOOT	478	233	191	300	337	280		1819
XX003163	EMERGENCY VEHICLE PRIORITY SYSTEM	EACH	1	1	1	1	1	1		6
XX003165	VIDEO CAMERA DETECTOR SYSTEM	EACH	1	1	1	1	1	1		6
XX004921	PEDESTRIAN PUSHBUTTON, SPECIAL	EACH	8	8	4	8				28
Z0050900	REMOVE CONCRETE FOUNDATION	EACH	8	8	6	8				30

PLOT DATE = Thu May 17 08:08:52 2007  
 FILE NAME = c:\p\projects\216590\c0389\p0.dgn  
 PLOT SCALE = 28.0000 / 1 IN.  
 USER NAME = gremson