

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* ROUTE 17 (US 52 / IL 64)
 ** (1,2)RS & (3,1)RS-1

SUMMARY OF QUANTITIES

Code No.	Item	Units	Total Quantity	← F →			
				80 % Fed. 20 % State 1 000-2A	100 % CITY Y060 UTILITIES	80 % Fed. 20 % State Y030-1E LIGHTING	80 % Fed. 20 % State SN 008-2019 X028-2A
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	30,068	30,068			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	178	178			
40600990	TEMPORARY RAMP	SQ YD	4,781	4,781			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N70	TON	45,049	45,049			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	4,034	4,034			
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	14,634	14,634			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5,022	5,022			
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	1,187	1,187			
44000100	PAVEMENT REMOVAL	SQ YD	12,236	12,236			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	24,289	24,289			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	81	81			
44000300	CURB REMOVAL	FOOT	66	66			
44000400	GUTTER REMOVAL	FOOT	18,004	18,004			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,198	1,198			
44000600	SIDEWALK REMOVAL	SQ FT	555	555			
44002805	ISLAND REMOVAL	SQ FT	517	517			
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	577	428			149
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	21,057	21,057			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	12,951	12,951			
48100100	AGGREGATE SHOULDERS, TYPE A	TON	52,430	52,430			
48203020	HOT-MIX ASPHALT SHOULDERS, 5 3/4"	SQ YD	46,531	46,531			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	2,778	2,778			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1				1
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1			
50104400	CONCRETE HEADWALL REMOVAL	EACH	42	42			
50105200	REMOVE EXISTING CULVERTS	EACH	13	13			
50105220	PIPE CULVERT REMOVAL	FOOT	161	161			
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	480	247			233
50800105	REINFORCEMENT BARS	POUND	16,197	1,639			14558
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,347	749			1598
51205200	TEMPORARY SHEET PILING	SQ FT	972	972			
51500100	NAME PLATES	EACH	6	5			1
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	2	2			
54001002	BOX CULVERT END SECTION, CULVERT NO.2	EACH	3	3			
54001003	BOX CULVERT END SECTION, CULVERT NO.3	EACH	1	1			
54001004	BOX CULVERT END SECTION, CULVERT NO.4	EACH	3	3			
54001005	BOX CULVERT END SECTION, CULVERT NO.5	EACH	1	1			

PLT DATE = Thu Nov 22 15:24:53 2007
 FILE NAME = C:\Users\7400\Documents\64560\summary.dgn
 PLT SCALE = 50.0000 / IN.
 USER NAME = cushmanbv

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY