

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* ROUTE 17 (US 52 / IL 64)
 ** (1,2)RS & (3,1)RS-1

SUMMARY OF QUANTITIES

Code No.	Item	Units	Total Quantity	← F →		
				80 % Fed. 20 % State 1 000-2A	100 % CITY Y060 UTILITIES	80 % Fed. 20 % State Y030-1E LIGHTING
54001006	BOX CULVERT END SECTION, CULVERT NO.6	EACH	6	6		
54003000	CONCRETE BOX CULVERTS	CU YD	148	21		127
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	152	152		
54010707	PRECAST CONCRETE BOX CULVERT 7' X 7'	FOOT	294			294
54010906	PRECAST CONCRETE BOX CULVERT 9' X 6'	FOOT	22	22		
54010908	PRECAST CONCRETE BOX CULVERT 9' X 8'	FOOT	92	92		
54020403	PRECAST CONCRETE BOX CULVERT 4' X 3' (M273)	FOOT	15	15		
54021006	PRECAST CONCRETE BOX CULVERT 10' X 6' (M273)	FOOT	189	188		
54213459	END SECTIONS 24"	EACH	15	15		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6	6		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	8	8		
54213678	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 33"	EACH	3	3		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	7	7		
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1		
54213711	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 66"	EACH	1	1		
54215454	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 54"	EACH	2	2		
54215550	METAL END SECTIONS 15"	EACH	92	92		
54215565	METAL END SECTIONS 30"	EACH	2	2		
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	18	18		
5422D060	PIPE CULVERTS, CLASS D, TYPE 2 60" (TEMPORARY)	FOOT	45	45		
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	52	52		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	5	5		
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	262	262		
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	278	278		
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	152	152		
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	167	167		
542A1111	PIPE CULVERTS, CLASS A, TYPE 2 66"	FOOT	35	35		
542A1933	PIPE CULVERTS, CLASS A, TYPE 3 48"	FOOT	62	62		
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	2,352	2,352		
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	419	419		
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	46	46		
54248515	CONCRETE COLLAR	EACH	3	3		
54390170	INSERTION CULVERT LINER 22"	FOOT	550	550		
54390200	INSERTION CULVERT LINER 28"	FOOT	218	218		
54390220	INSERTION CULVERT LINER 32"	FOOT	270	270		
55100500	STORM SEWER REMOVAL 12"	FOOT	216	216		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT.	DRAWN BY	
DATE	CHECKED BY	

SUMMARY OF QUANTITIES

PLOT DATE = Thu Mar 22 15:44:53 2007
 FILE NAME = C:\projects\1207480\1207480.dgn
 USER NAME = cshenbu