CONTRACT NO. 64560

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* ROUTE 17 (US 52 / IL 64)
** (1,2)RS & (3,1)RS-1

SUMMARY OF QUANTITIES

Code No.	Item	Units	Total Quantity	F 80 % Fed. 20 % State I 000-2A	100 % CITY Y060 UTILITIES	← F → 80 % Fed. 20 % State Y030-1E LIGHTING	80 % Fed. 20 % State SN 008-2019 X028-2A
55100900	STORM SEWER REMOVAL 18"	FOOT	96	96			
55101200	STORM SEWER REMOVAL 24"	FOOT	88	88			
55101600	STORM SEWER REMOVAL 36"	FOOT	340	340			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	126	126			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	8	8			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	45	45			
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	35	35			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	341	341			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	153	153			
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	194	194			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	252	252			
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	241	241			
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	23	23			
55036900	STORM SEWERS, TYPE 3, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 53, RISE 34	FOOT	420	420			
552A0900	STORM SEWERS JACKED IN PLACE, CLASS A 24"	FOOT	94	94			
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1		1		
* 56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1		1		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	355	355			
60107600	PIPE UNDERDRAINS 4"	FOOT	97,577	97,577			
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	5,004	5,004			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11			
60224090	MANHOLES, TYPE A, 6'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1	1			
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60228400	MANHOLES, SPECIAL	EACH	1	1			
60240361	INLETS, TYPE B, WITH MEDIAN INLET (604101)	EACH	2	2			
60242400	INLETS, SPECIAL	EACH	7	7			
60242700	INLETS, SPECIAL, NO. 3	EACH	14	14			
60242800	INLETS, SPECIAL, NO. 4	EACH	1	1			
60255500	MANHOLES TO BE ADJUSTED	EACH	5	2	3		
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3		3		
60262405	INLETS TO BE ADJUSTED WITH NEW MEDIAN INLET (604101)	EACH	3	3			
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2			
60500040	REMOVING MANHOLES	EACH	4	4			
60500060	REMOVING INLETS	EACH	6	6			
60500065	REMOVING INLETS, SPECIAL	EACH	34	34			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	44	44			
60602500	CONCRETE GUTTER, TYPE A	FOOT	126	126			

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

SUMMARY OF QUANTITIES

PLOT DATE = Thu Mar 22 15:43:01 2007
FILE NAME = C:\projects\p207400\d07400cvr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = cushmanbw