

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	24
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* ROUTE 17 (US 52 / IL 64)
 ** (1,2)RS & (3,4)RS-1

SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION	OFFSET	
6	368 + 36	61	LT
6	369 + 26	92	LT
6	369 + 43	82	LT
6	369 + 56	84	LT
14	369 + 61	69	LT
8	369 + 85	77	LT
13	369 + 72	70	LT
11	369 + 95	70	LT
14	370 + 12	48	LT
14	370 + 13	49	LT
14	370 + 14	50	LT
6	370 + 17	64	LT
13	370 + 78	73	LT
13	370 + 88	72	LT
13	370 + 97	70	LT
10	371 + 7	63	LT
13	371 + 15	67	LT
10	371 + 23	66	LT
12	371 + 33	60	LT
14	371 + 49	63	LT
12	389 + 92	52	LT
8	389 + 95	80	LT
12	390 + 16	53	LT
12	390 + 16	56	LT
8	390 + 17	50	LT
8	390 + 23	55	LT
12	390 + 28	50	LT
8	390 + 28	56	LT
14	413 + 23	47	LT
8	441 + 4	53	LT
9	441 + 12	58	LT
10	441 + 21	66	LT
10	441 + 29	47	LT
6	441 + 30	51	LT
8	441 + 35	44	LT
10	441 + 35	42	LT
11	441 + 46	41	LT
14	441 + 91	45	LT
9	442 + 3	39	LT
12	442 + 1	57	LT
11	442 + 3	64	LT
11	471 + 64	43	RT
8	471 + 85	43	RT
9	472 + 1	43	RT
6	448 + 95	87	LT
6	449 + 35	62	LT
6	449 + 36	63	LT
6	449 + 60	69	LT
6	449 + 68	65	LT
7	449 + 70	67	LT
6	449 + 70	66	LT
7	449 + 71	67	LT
6	449 + 71	65	LT
7	449 + 80	64	LT
6	449 + 81	61	LT
7	449 + 85	58	LT
6	449 + 85	62	LT
6	450 + 5	65	LT
11	564 + 65	50	LT
12	579 + 26	85	LT
11	579 + 48	84	LT
8	580 + 21	60	RT
8	580 + 21	61	RT
8	580 + 22	60	RT
8	580 + 22	61	RT
10	580 + 35	92	LT
10	580 + 40	85	LT
10	580 + 41	86	LT
8	580 + 42	92	LT
6	580 + 67	83	LT
11	580 + 75	74	LT
8	580 + 76	89	LT
10	581 + 23	46	LT
11	17 + 85	26	RT
15	17 + 89	27	RT
7	17 + 96	25	RT
9	17 + 99	24	RT
12	18 + 4	23	RT
10	18 + 13	27	RT
747	TOTAL		

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION	OFFSET	
15	389 + 98	55	LT
18	390 + 00	56	LT
24	473 + 96	86	RT
24.5	473 + 96	107	LT
34.5	482 + 73	52	RT
25	527 + 14	83	RT
20	527 + 14	103	RT
16	580 + 40	96	LT
16	580 + 41	96	LT
35	580 + 47	108	LT
36	580 + 87	88	LT
16	580 + 93	110	RT
24	580 + 99	106	RT
22	580 + 99	113	RT
21	581 + 8	107	RT
21	581 + 28	126	RT
18	581 + 33	118	RT
20.5	581 + 33	119	RT
16	18 + 17	26	RT
422.5	TOTAL		

20100500 TREE REMOVAL - ACRES

ACRES	LOCATION				
0.78	205 + 00	-	209	+ 00	RT
1.64	213 + 00	-	219	+ 94	RT
1.32	226 + 34	-	235	+ 00	RT
0.30	236 + 7	-	238	+ 90	RT
0.66	254 + 74	-	260	+ 00	RT
0.355	272 + 97	-	276	+ 74	RT
0.151	299 + 70	-	303	+ 60	RT
0.254	312 + 22	-	315	+ 28	RT
0.037	344 + 51	-	345	+ 00	LT
0.041	345 + 00	-	345	+ 84	RT
0.27	350 + 53	-	355	+ 85	LT
0.042	361 + 13	-	361	+ 61	LT
0.053	363 + 32	-	363	+ 77	LT
0.164	364 + 63	-	367	+ 32	LT
0.348	445 + 55	-	448	+ 63	LT
0.045	530 + 99	-	532	+ 30	LT
0.002	532 + 64	-	533	+ 13	LT
0.691	565 + 70	-	577	+ 87	LT
0.137	573 + 77	-	577	+ 87	RT
0.039	598 + 13	-	599	+ 72	LT
7.0	TOTAL				

20101000 TEMPORARY FENCE

FOOT	LOCATION				
120.0	17 + 80	-	19	+ 00	SCENIC BLUFF RD. (SOUTH)
507.0	469 + 2	-	471	+ 20	RT
627.0	TOTAL				

20200100 EARTH EXCAVATION

CU. YD	LOCATION				
226.9	529 + 00	-	536	+ 00	IL 78 Stage 5
227	TOTAL				

20800150 TRENCH BACKFILL

CU. YD	LOCATION	
10.8	INLET1 TO MHR1	S Jackson St
11.9	INLET3 TO MHL1	S Jackson St
0.7	INLET2 TO MHR1	S Jackson St
2.6	MHR1 TO MHL1	S Jackson St
12.1	MHL1 TO OUTLET	S Jackson St
4.6	INL2 TO INL3	COMMERCIAL ST.
1.4	INR7 TO INR6	IL 78
4.1	INR4 TO INR3	IL 78
2.5	INR8 TO INR9	IL 78
4.4	INR9 TO INR10	IL 78
9.5	INR10 TO INR11	IL 78
16.2	INR13 TO MHR2	IL 78
4.4	INL6 TO INL7	IL 78
6.9	INL5 TO INL4	COMMERCIAL ST.
4.7	INR5 TO INR4	COMMERCIAL ST.
3.5	INR6 TO INR4	COMMERCIAL ST.
14.2	JNR3 TO INR2	IL 78
16.9	INR11 TO INR12	IL 78
4.8	INL7 TO INL8	IL 78
11.7	INR2 TO MHL1	IL 78
9.9	INL8 TO INL9	IL 78
15.4	INL9 TO INL10	IL 78
6.6	MHL2 TO INL3	COMMERCIAL ST.
13.5	INL10 TO INR12	IL 78
38.0	INR12 TO MHR1	IL 78
9.1	INR1 TO INL1	IL 78
30.3	INL1 TO MHL1	IL 78
7.4	MHL1 TO INL2	IL 78
10.8	INL3 TO INL4	COMMERCIAL ST.
18.6	INL4 TO MHL3	COMMERCIAL ST.
307	TOTAL	

25000750 MOWING

ACRE	LOCATION	
50	Entire Job	
50	TOTAL	

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION				
4	252 + 00	-	253	+ 50	RT
7	282 + 00	-	285	+ 00	RT & LT
4	294 + 50	-	296	+ 00	RT
3	308 + 00	-	310	+ 00	RT
13	369 + 00	-	372	+ 50	RT & LT
11	405 + 00	-	410	+ 00	RT & LT
11	426 + 25	-	429	+ 50	LT
7	435 + 75	-	437	+ 25	RT
12	484 + 00	-	495	+ 00	RT
3	502 + 00	-	504	+ 00	RT
21	566 + 00	-	577	+ 50	RT & LT
1	583 + 00	-			RT
14	587 + 50	-	595	+ 00	RT & LT
24	603 + 00	-	613	+ 00	RT & LT
8	616 + 00	-	623	+ 00	LT
1	639 + 00	-			LT
76	1002 + 00	-	1015	+ 25	RT & LT Quarry Rd
12	36 + 50	-	39	+ 25	LT Quarry Entrance
11	1105 + 00	-	1107	+ 50	RT & LT OIL Valley School Rd
2	1201 + 75	-			RT & LT OLD 52 W
2	1805 + 50	-			RT & LT OLD 52 E
4	609 + 50	-	614	+ 25	RT & LT IL 78
1	1508 + 00	-			RT East St.
21	1600 + 25	-	1604	+ 00	RT & LT Benton St.
273	TOTAL				

PLOT DATE * Thu Mar 22 15:05:59 2007
 FILE NAME * C:\projects\2007\08\ad7400c-vr.dgn
 PLOT SCALE * 50.0000 / IN.
 USER NAME * c:\users\m...

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
		DRAWN BY
		CHECKED BY