

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	45
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* ROUTE 17 (US 52 / IL 64)
 ** (1,2)RS & (3,1)RS-1

SUB-BASE SCHEDULE

Location	Remarks	Area Sq Yd	Breaker Run Depth Inch	CA-02 Depth Inch	CA-06 Depth Inch	31100910	31100920	31100935	31100965	31103000	28200200
						Sub-base Granular Type A 12"	Sub-base Granular Type A 15"	Sub-base Granular Type A 18"	Sub-base Granular Type A 24"	Sub-base Granular (Special)	Filter Fabric 80Z
US 52/IL 64											
RT Sta 456 + 42 to 486 + 0	Realignment	3230.0	21		3				3230.0		
LT Sta 529 + 00 to 536 + 00	Shoulder - Stage 1	322.9		9	3	322.9					
RT Sta 529 + 00 to 536 + 00	Shoulder - Stage 1A	325.9		9	3	325.9					
LT Sta 544 + 13 to 551 + 00	Turn Lane	1037.8	12		3		1037.8				
RT Sta 549 + 33 to 551 + 00	Turn Lane	169.5	12		3		169.5				
RT Sta 551 + 00 to 554 + 50	Turn Lane	675.3	21		3				675.3		
LT Sta 551 + 00 to 554 + 50	Turn Lane	718.4	21		3				718.4		
RT Sta 554 + 50 to 559 + 50	Turn Lane	483.9	12		3		483.9				
LT Sta 554 + 50 to 559 + 50	Turn Lane	838.0	12		3		838.0				
RT Sta 559 + 50 to 566 + 50	Turn Lane	984.4		9	3	984.4					
LT Sta 559 + 50 to 566 + 50	Turn Lane	1785.7		9	3	1785.7					
LT Sta 566 + 50 to 570 + 50	Turn Lane	885.8	12		3		885.8				
LT Sta 570 + 50 to 576 + 95	Turn Lane	1009.3	21		3				1009.3		
LT Sta 586 + 67 to 589 + 50	Turn Lane	390.8		9	3	390.8					
LT Sta 589 + 50 to 592 + 50	Turn Lane	551.4	12		3		551.4				
LT Sta 592 + 50 to 595 + 99	Turn Lane	409.4		9	3	409.4					
LT Sta 604 + 80 to 616 + 50	Turn Lane	1593.9		9	3	1593.9					
RT Sta 605 + 26 to 616 + 50	Turn Lane	1268.5		9	3	1268.5					
RT Sta 616 + 50 to 617 + 50	Turn Lane	125.5	12		3		125.5				
LT Sta 616 + 50 to 617 + 50	Turn Lane	277.6	12		3		277.6				
LT Sta 617 + 50 to 623 + 88	Turn Lane	1037.9		9	3	1037.9					
RT Sta 617 + 50 to 623 + 88	Turn Lane	712.5		9	3	712.5					
LT Sta 641 + 46 to 643 + 50	Turn Lane	401.3	21		3				401.3		
LT Sta 643 + 50 to 647 + 6	Turn Lane	521.7		9	3	521.7					

Plot Date : Thu Mar 22 15:27:03 2007
 File Name : C:\p1\12277463\12277463.dgn
 Plot Scale : 50.0000 / IN.
 User Name : csherman

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY

SUB-BASE SCHEDULE