

# SUB-BASE SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	46
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

\* ROUTE 17 (US 52 / IL 64)  
 \*\* (1,2)RS & (3,1)RS-1

Location	Remarks	Area	Breaker Run Depth	CA-02 Depth	CA-06 Depth	31100910	31100920	31100935	31100965	31103000	28200200
						Sub-base Granular Type A 12"	Sub-base Granular Type A 15"	Sub-base Granular Type A 18"	Sub-base Granular Type A 24"	Sub-base Granular (Special)	Filter Fabric 80Z
		Sq Yd	Inch	Inch	Inch	Sq Yd	Sq Yd	Sq Yd	Sq Yd	Sq Yd	Sq Yd
<b>SCENIC BLUFF RD</b>											
Sta 17 + 65 to 19 + 88	South Leg	1088.5		9	3	1088.5					
Sta 20 + 12 to 32 + 50	North Leg	1159.2		9	3	1159.2					
<b>DAUPHN RD</b>											
Sta 40 + 12 to 41 + 00	North Leg	660.5		9	3	660.5					
<b>ROBERTS RD</b>											
Sta 50 + 12 to 51 + 50	North Leg	758.2		9	3	758.2					
<b>FRONTAGE RD</b>											
Sta 329 + 00 to 329 + 50	South Leg	375.3		9	3	375.3					
<b>FRONTAGE RD</b>											
Sta 342 + 20 to 342 + 60	South Leg	121.7		9	3	121.7					
<b>JACOBSTOWN RD</b>											
Sta 60 + 12 to 61 + 75	North Leg	1048.3		9	3	1048.3					
<b>FRONTAGE RD</b>											
Sta 356 + 50 to 356 + 70	South Leg	124.0		9	3	124.0					
<b>BECKER RD</b>											
Sta 67 + 95 to 69 + 88	South Leg	824.2		9	3	824.2					
<b>FRONTAGE RD</b>											
Sta 385 + 00 to 385 + 15	North Leg	158.1		9	3	158.1					
<b>SEVEN HILLS RD</b>											
Sta 78 + 65 to 79 + 88	South Leg	809.0		9	3	809.0					
<b>FRONTAGE RD</b>											
Sta 396 + 00 to 396 + 15	North Leg	150.6		9	3	150.6					
<b>FRONTAGE RD</b>											
Sta 403 + 00 to 403 + 15	North Leg	155.8		9	3	155.8					
<b>QUARRY RD</b>											
Sta 1001 + 17 to 1002 + 50	North Leg w/ Turn Lane	1776.0	15		3			1776.0			1776.0
Sta 1002 + 50 to 1011 + 00	North Leg	2371.5	36		3					2371.5	2371.5
Sta 1011 + 00 to 1015 + 25	North Leg	1133.3	21		3				1133.3		1133.3
<b>QUARRY RD Entrance</b>											
Sta 36 + 00 to 39 + 88	North Leg	1412.1	21		3				1412.1		
<b>PRESTON RD</b>											
Sta 88 + 50 to 89 + 88	South Leg	770.8		9	3	770.8					
<b>OIL VALLEY SCHOOL RD</b>											
Sta 1103 + 55 to 1108 + 9	South Leg	1548.9		9	3	1548.9					1548.9
<b>OLD 52 W</b>											
Sta 1200 + 40 to 1202 + 68	North Leg	841.0		9	3	841.0					
<b>MILL RD</b>											
Sta 1707 + 00 to 1709 + 98	South Leg	1553.9		9	3	1553.9					
Sta 1710 + 22 to 1712 + 75	North Leg	1561.7		9	3	1561.7					
<b>MCLTON RD</b>											
Sta 1804 + 50 to 1807 + 40	South Leg	1845.6		9	3	1845.6					
<b>IL RTE 78</b>											
Sta 600 + 37 to 608 + 6	South Leg (Full Depth Pavement)	5398.1	12		3		5398.1				
Sta 608 + 32 to 617 + 00	Widening RT	1174.3	21		3				1174.3		
Sta 608 + 32 to 617 + 00	Widening LT	1499.5	21		3				1499.5		
<b>COMMERCIAL ST</b>											
Sta 58 + 40 to 58 + 99	West Leg	200.8		9	3	200.8					
Sta 60 + 85 to 61 + 20	East Leg	117.3		9	3	117.3					
<b>JACKSON ST</b>											
Sta 8 + 29 to 9 + 88	South Leg	1238.7		9	3	1238.7					
Sta 10 + 27 to 11 + 80	North Leg	685.1		9	3	685.1					
<b>EAST ST</b>											
Sta 1507 + 00 to 1509 + 18	South Leg	959.5		9	3	959.5					
Sta 1509 + 62 to 1511 + 55	North Leg	1047.1		9	3	1047.1					
<b>BENTON ST</b>											
Sta 1600 + 13 to 1604 + 75	North Leg	1888.6		9	3	1888.6					
<b>STAGE II</b>											
Sta 448 + 27 to 448 + 83	Stage II	19.0		9	3	19.0					
<b>STAGE III</b>											
Sta 448 + 19 to 448 + 68	Stage III	115.0		9	3	115.0					
<b>TOTALS</b>											
						31180	9768	1776	11254	2371	6830

PLOT DATE = Thu Mar 22 15:27:23 2007  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = dushman/bv

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT.    DRAWN BY HORIZ.            CHECKED BY DATE

## SUB-BASE SCHEDULE