

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	53
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE

* ROUTE 17 (US 52 / IL 64)
** (1,1RS & 1,1RS-1)

LOCATION	20200100	20400800			20200200	21101505	21101615	20600300		
	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	FURNISHED EXCAVATION	ROCK EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL EXCAVATION & PLACEMENT	TOPSOIL FURNISHED & PLACE 4"	QUARRY RUN GRANULAR EMBANKMENT
	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(SY YD)	TON
170+00.00 TO 184+00.00	402.0	301.5	64.8	236.7			157.4			
184+00.00 TO 199+00.00	653.7	490.3	860.9	-370.6			483.3			
199+00.00 TO 214+00.00	1792.8	1344.6	5590.6	-4246.0			1078.1			
205+00.00 TO 208+00.00										3400.0
214+00.00 TO 229+00.00	418.7	314.0	16857.4	-16543.4			1262.4			
229+00.00 TO 244+00.00	324.4	243.3	10084.1	-9840.8			1512.0			
232+00.00 TO 234+00.00										3884.9
244+00.00 TO 259+00.00	556.5	417.4	4260.0	-3842.6			1020.0			
259+00.00 TO 274+00.00	460.0	345.0	1246.7	-901.7			519.6			
274+00.00 TO 289+00.00	491.3	368.5	1383.3	-1014.8			721.1			
289+00.00 TO 304+00.00	645.7	484.3	1068.1	-583.8			483.5			
304+00.00 TO 319+00.00	663.3	497.5	1443.1	-945.6			438.5			
319+00.00 TO 334+00.00	305.9	229.4	1164.1	-934.7			503.0			
334+00.00 TO 349+00.00	492.2	369.2	891.7	-522.6			573.3			
349+00.00 TO 364+00.00	305.2	228.9	2507.6	-2278.7			683.9			
364+00.00 TO 379+00.00	3283.0	2462.3	1927.6	534.7			1278.3			
379+00.00 TO 394+00.00	362.0	271.5	376.1	-104.6			255.6			
394+00.00 TO 409+00.00	3136.3	2352.2	1502.2	850.0			1166.5			
409+00.00 TO 424+00.00	1966.9	1475.2	284.3	1190.9			602.6			
424+00.00 TO 439+00.00	2210.2	1657.7	120.0	1537.7			511.9			
439+00.00 TO 454+00.00	1624.8	1218.6	2380.2	-1161.6			662.2			
441+56.00 TO 441+95.0-0										358.3
454+00.00 TO 469+00.00	2844.3	2133.2	713.0	1420.2			711.1			
469+00.00 TO 484+00.00	2597.6	1948.2	1422.4	525.8			763.0			
484+00.00 TO 499+00.00	1435.2	1076.4	98.5	977.9			473.9			
499+00.00 TO 514+00.00	679.4	509.6	246.3	263.3			283.1			
514+00.00 TO 529+00.00	530.2	397.7	266.1	131.6			309.1			
529+00.00 TO 544+00.00	397.4	298.1	443.5	-145.5			368.7			
544+00.00 TO 559+00.00	2099.8	1574.9	1832.2	-257.4			480.6			
559+00.00 TO 574+00.00	5810.4	4357.8	3330.0	1027.8			1201.3			
574+00.00 TO 589+00.00	2687.4	2015.6	18890.7	-16875.2			2049.8			
589+00.00 TO 604+00.00	2493.0	1869.8	3690.4	-1820.7			1256.7			
604+00.00 TO 619+00.00	2878.1	2158.6	1829.6	329.0			892.0			
619+00.00 TO 634+00.00	1390.4	1042.8	1437.2	-394.4			713.5			
634+00.00 TO 649+00.00	1218.4	913.8	1905.8	-992.0			1076.7			
649+00.00 TO 658+73.00	242.2	181.7	369.4	-187.8						

PLOT DATE = Thu Mar 22 15:27:05 2007
FILE NAME = C:\projects\14297480\cd7480.dgn
USER NAME = cadmanba

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT.
DATE: HORIZ.

DRAWN BY
CHECKED BY

EARTHWORK SCHEDULE