

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
..	..	CARROLL	548	54
STA.		TO STA.		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

EARTHWORK SCHEDULE

* ROUTE 17 (US 52 / IL 64)
 ** (1,2)RS & (3,1)RS-1

LOCATION	20200100	EARTHWORK			20400800	20200200	21101505	21101615	20600300	
	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	FURNISHED EXCAVATION	ROCK EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL EXCAVATION & PLACEMENT	TOPSOIL FURNISHED & PLACE 4"	QUARRY RUN GRANULAR EMBANKMENT
	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(SY YD)	TON
SCENIC BLUFF RD. (SOUTH) 17+65.00 TO 19+50.00	398.9	299.2	38.6	260.6			75.7			
SCENIC BLUFF RD. (NORTH) 30+50.00 TO 32+50.00	230.9	173.2	36.7	136.5			46.9			
DAUPHIN RD. 40+50.00 TO 41+00.00	152.8	114.6	10.4	104.2			20.1			
ROBERTS RD. 50+50.00 TO 51+50.00	465.2	348.9	1.3	347.6			24.4			
JACOBSTOWN RD. 60+50.00 TO 61+75.00	484.5	363.4	1.7	361.7			62.2			
BECKER RD. 67+95.00 TO 69+50.00	786.9	590.2	400.4	189.8			126.6			
SEVEN HILLS RD. 78+65.00 TO 79+50.00	102.1	76.6	1.0	75.6			12.4			
QUARRY RD. 1001+50.00 TO 1015+25.00	30741.0	23055.8	261.1	22794.7		3156.2	1324.4	15900.5		
QUARRY ENTRANCE 36+10.00 TO 39+50.00	16846.6	12635.0	76.6	12558.4		5879.1	625.6	6669.1		
PRESTON RD. 88+50.00 TO 89+50.00	237.0	177.8	3.1	174.7			20.2			
OIL VALLEY SCHOOL RD. 1103+55.00 TO 1107+75.00	512.0	384.0	303.1	80.9			168.1			
OLD 52W 1200+75.00 TO 1202+67.95	632.6	474.5	169.9	304.6			147.3			
MILL RD. (SOUTH) 1707+00.00 TO 1709+75.00	550.2	412.7	99.2	313.5			100.6			
MILL RD. (NORTH) 1710+50.00 TO 1712+75.00	494.5	370.9	21.4	349.5			43.2			
OLD 52E 1804+50.00 TO 1807+00.00	772.4	579.3	36.9	542.4			125.4			

PLOT DATE = Thu, Mar 23, 15:27:05, 2007
 FILE NAME = C:\pwork\64560\207408\087408.dgn
 PLOT SCALE = 50.00000 / IN.
 USER NAME = cshamby