

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	55
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* ROUTE 17 (US 52 / IL 64)
 ** (1,2)RS & (3,1)RS-1

EARTHWORK SCHEDULE

LOCATION	20200100	EARTHWORK			20400800	20200200		21101505	21101615	20600300
	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	FURNISHED EXCAVATION	ROCK EXCAVATION	TOPSOIL PLACEMENT	TOPSOIL EXCAVATION & PLACEMENT	TOPSOIL FURNISHED & PLACE 4"	QUARRY RUN GRANULAR EMBANKMENT
	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(SY YD)	TON
IL 78 (SOUTH) 600+00 TO 607+50.00	4047.5	3035.6	1357.5	1678.1			294.5			
IL 78 (NORTH) 609+00.00 TO 619+00.00	4259.0	3194.3	3507.3	-313.1			1024.6			
JACKSON ST. (SOUTH) 8+04.67 TO 9+50.00	337.7	253.3	12.5	240.8			33.8			
JACKSON ST. (NORTH) 10+50.00 TO 11+65.00	399.8	299.9	1.1	298.8			46.4			
EAST ST. (SOUTH) 1507+00.00 TO 1509+00.00	376.9	282.7	0.0	282.7			44.3			
EAST ST. (NORTH) 1510+00.00 TO 1511+55.00	252.8	189.6	11.1	178.5			40.6			
BENTON ST. 1600+50.00 TO 1604+75.00	1949.7	1462.3	8.6	1453.7			183.6			
COMMERCIAL ST. (WEST) 58+39.85 TO 59+50.00	476.2	357.2	6.7	350.5			23.6			
COMMERCIAL ST. (EAST) 60+50.00 TO 61+20.00	349.5	262.1	0.0	262.1			23.5			
TOTALS	113255.4	84941.6	96854.1	-11912.6	11912.6	9035.3	29130.7	22569.6	59049.9	7643.2

PLOT DATE = Thu Mar 22 15:27:46 2007
 FILE NAME = C:\projects\1527488\1527488.dgn
 USER = schanabaw

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT.	DRAWN BY	
DATE	CHECKED BY	