

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	56
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SEEDING SCHEDULE

\* ROUTE 17 (US 52 / IL 64)  
 \*\* (1,2)RS & (3,1)RS-1

LOCATION	LEFT								
	25000210	25001310	25000400	25000500	25000600	25100115	25100125	25100630	28000250
	SEEDING CLASS 2A ACRES	SEEDING CLASS 4 ACRES	NITROGEN FERTILIZER NUTRIENT LBS	PHOSPHORUS FERTILIZER NUTRIENT LBS	POTASSIUM FERTILIZER NUTRIENT LBS	MULCH METHOD 2.0 ACRES	MULCH METHOD 3.0 ACRES	EROSION CONTROL BLANKET SQ. YD.	TEMPORARY EROSION CONTROL SEEDING LBS
MAINLINE									
170+00.0 TO 184+00.0	0.15	0.00	13.5	13.5	13.5	0.15			60.0
184+00.0 TO 199+00.0	0.65	0.02	60.3	60.3	60.3	0.67			268.0
199+00.0 TO 214+00.0	0.31	0.04	31.5	31.5	31.5	0.35			140.0
214+00.0 TO 229+00.0	0.27	0.00	24.3	24.3	24.3	0.27			108.0
229+00.0 TO 244+00.0	0.42	0.00	37.8	37.8	37.8	0.42			168.0
244+00.0 TO 259+00.0	0.26	0.00	23.4	23.4	23.4	0.26			104.0
259+00.0 TO 274+00.0	0.25	0.00	22.5	22.5	22.5	0.25			100.0
274+00.0 TO 289+00.0	0.24	0.05	26.1	26.1	26.1	0.29			116.0
289+00.0 TO 304+00.0	0.15	0.01	14.4	14.4	14.4	0.16			64.0
304+00.0 TO 319+00.0	0.10	0.00	9.0	9.0	9.0	0.10			40.0
319+00.0 TO 334+00.0	0.46	0.00	41.4	41.4	41.4	0.46			184.0
334+00.0 TO 349+00.0	0.39	0.00	35.1	35.1	35.1	0.39		1887.6	156.0
349+00.0 TO 364+00.0	0.85	0.01	77.4	77.4	77.4	0.86		4162.4	344.0
364+00.0 TO 379+00.0	0.39	0.43	73.8	73.8	73.8	0.82		3968.8	328.0
379+00.0 TO 394+00.0	0.18	0.05	20.7	20.7	20.7	0.23			92.0
394+00.0 TO 409+00.0	0.48	0.11	53.1	53.1	53.1	0.59			236.0
409+00.0 TO 424+00.0	0.22	0.04	23.4	23.4	23.4	0.26			104.0
424+00.0 TO 439+00.0	0.33	0.09	37.8	37.8	37.8	0.42			168.0
439+00.0 TO 454+00.0	0.61	0.10	63.9	63.9	63.9	0.71		3436.4	284.0
454+00.0 TO 469+00.0	0.47	0.36	74.7	74.7	74.7	0.83			332.0
469+00.0 TO 484+00.0	0.51	0.06	51.3	51.3	51.3		0.57		228.0
484+00.0 TO 499+00.0	0.15	0.00	13.5	13.5	13.5	0.15			60.0
499+00.0 TO 514+00.0	0.11	0.00	9.9	9.9	9.9	0.11			44.0
514+00.0 TO 529+00.0	0.14	0.00	12.6	12.6	12.6	0.14			56.0
529+00.0 TO 544+00.0	0.21	0.02	20.7	20.7	20.7	0.23			92.0
544+00.0 TO 559+00.0	0.41	0.02	38.7	38.7	38.7	0.43			172.0
559+00.0 TO 574+00.0	0.66	0.64	117.0	117.0	117.0	1.30			520.0
574+00.0 TO 589+00.0	1.36	0.34	153.0	153.0	153.0	1.70			680.0
589+00.0 TO 604+00.0	0.85	0.15	89.8	89.8	89.8	1.00		4830.3	399.2
604+00.0 TO 619+00.0	0.71	0.23	84.6	84.6	84.6	0.94			376.0
619+00.0 TO 634+00.0	0.42	0.14	50.4	50.4	50.4	0.56			224.0
634+00.0 TO 657+28.0	1.22	0.09	117.9	117.9	117.9	1.31			524.0

PLOT DATE = Thu Mar 22 15:27:05 2007  
 FILE NAME = C:\projects\1207488\1207488.dwg  
 USER NAME = cadmanba

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

## SEEDING SCHEDULE