

F.A.W. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5789	338&401-1-FR	ROCK ISLAND	30	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN		1000-1A	Y031-1F
			TOTAL QUANTITY	100% STATE	100% STATE	100% STATE
20200100	EARTH EXCAVATION	CU YD	472	472		
21101625	TOPSOIL FURNISH AND PLACE, 6"	SO YD	972	972		
25200100	SODDING	SQ YD	972	972		
25200200	SUPPLEMENTAL WATERING	UNIT	20	20		
28000500	INLET AND PIPE PROTECTION	EACH	3	3		
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SO YD	572	572		
40600625	LEVELING BINDER (MACHINE MEATHOD), N50	TON	11	11		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT	SO YD	75	75		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	46	46		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	50	50		
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SO YD	497	497		
44000100	PAVEMENT REMOVAL	SO YD	21	21		
44004250	PAVED SHOULDER REMOVAL	SO YD	70	70		
44200919	CLASS B PATCHES, TYPE II, 7 INCH	SO YD	28	28		
44213200	SAW CUTS	FOOT	156	156		
50105220	PIPE CULVERT REMOVAL	FOOT	58	58		
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	9	9		
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	12	12		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	79	79		
55034200	STORM SEWERS, TYPE 1 REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 23, RISE 14	FOOT	21	21		
55100700	STORM SEWER REMOVAL 15"	FOOT	16	16		
* 56109210	WATER VALVES TO BE ADJUSTED	EACH	1	1		
60107600	PIPE UNDERDRAINS 4"	FOOT	50	50		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1	1		
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1		
60242801	INLETS, SPECIAL, NO. 5	EACH	2	2		
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60500060	REMOVING INLETS	EACH	1	1		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	266	266		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1685	1685		
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	204	204		
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	60	60		
* 80501000	SERVICE INSTALLATION, (SPECIAL)	EACH	1			1

* SPECIALTY ITEM

PLOT DATE = Wed Mar 21 08:51:02 2007
 FILE NAME = c:\projects\2007\385\061386.dgn
 USER = mgj/11
 USER NAME = mgj/11