CONTRACT NO. 66400

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1279	*	LASALLE	43	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*1-RS, (106,107)RS-2, 108 RS-1 & I

ENTRANCES AND SIDE ROAD SCHEDULE

STATION	ENTRANCE TYPE	SIDE	AREA	EXISTING SURFACE	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	INCIDENTAL HOT-MIX ASPHALT SURFACING	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMP RAMP	EMBANKMENT
			SQ YD		SQ YD	TON	GALLON	TON	SQ YD	CU YD
1012+62.25	PE	LT	29.36	BIT/AGG	7.26	3.1	2.3	0.1		
1025+09.83	CE	RT	50.00	AGG		5.3	18.8	0.1		
1053+07.87	SD RD	LT	150.40	OIL & CHIP		8.4	12.0	0.3		3.0
1053+12.09	SD RD	RT	188.00	BIT	57.78	19.7	15.0	0.4	14.4	3.0
1079+53.15	PE	LT	31.14	BIT	8.01	3.3	2.5	0.1		
1079+59.19	SD RD	RT	160.67	BIT/AGG	45.33	16.9	12.9	0.3	11.3	3.0
1088+63.32	SD RD	RT	146.25	BIT	47.87	15.4	11.7	0.3	12.0	3.0
1101+30.33	PE	RT	33.84	AGG		3.6	12.7	0.1		
1102+08.00	CE	RT	39.60	BIT	11.40	4.2	3.2	0.1		
1106+15.23	SD RD	LT	178.28	OIL & CHIP		10.0	14.3	0.4		3.0
1112+46.73	PE	RT	37.78	BIT	10.67	4.0	3.0	0.1		
1114+48.00	PE	RT	29.89	AGG		3.1	11.2	0.1		
1117+55.98	FE	LT	26.62	BIT/ AGG	6.22	2.8	2.1	0.1		
1128+84.80	PE	LT	28.89	BIT/ AGG	7.11	3.0	2.3	0.1		
1130+36.99	PE	RT	30.00	AGG		3.2	11.3	0.1		
1131+00.26	PE	RT	33.33	BIT/AGG	8.89	3.5	2.7	0.1		
1135+48.56	PE	RT	44.44	BIT/AGG	13.33	4.7	3.6	0.1		
1160+96.60	SD RD	RT	104.55	BIT/AGG	40.00	11.0	8.4	0.2	10.0	3.0
1175+34.18	CE	RT	141.50	CONC	NO WORK			0.3		
1181+01.45	SD RD	LT	206.75	BIT	65.49	21.7	16.5	0.4	16.4	3.0
1181+33.95	PE	RT	33.33	BIT/AGG	8.89	3.5	2.7	0.1		
1183+54.03	PE	RT	66.72	AGG		7.0	25.0	0.1		
1185+61.20	PE	LT	44.44	BIT/AGG	13.33	4.7	3.6	0.1		
1187+45.19	SD RD	RT	108.17	BIT/AGG	50.00	11.4	8.7	0.2	12.5	3.0
1187+87.11	PE	LT	33.33	BIT	8.89	3.5	2.7	0.1		
1189+88.53	SD RD	RT	112.83	BIT/AGG	46.44	11.8	9.0	0.2	11.6	3.0
1200+43.39	SD RD	RT	184.00	BIT	67.11	19.3	14.7	0.4	16.8	3.0
1205+36.03	SD RD	LT	150.95	BIT	100.63	15.8	12.1	0.3	15.1	3.0
1207+55.26	SD RD	LT	132.67	BIT	26.22	13.9	10.6	0.3	6.6	3.0
1212+33.55	PE	LT	33.89	AGG		3.6	12.7	0.1		
1213+17.19	PE	RT	37.78	AGG		4.0	14.2	0.1		
1213+51.76	PE	RT	37.78	BIT	10.67	4.0	3.0	0.1		
1215+05.80	SD RD	LT	119.50	BIT/AGG	50.00	12.5	9.6	0.2	12.5	3.0
1215+96.23	PE	RT	37.78	BIT / AGG	10.67	4.0	3.0	0.1		
1217+25.53	PE	RT	34.44	AGG		3.6	12.9	0.1		
1217+65.33	PE	LT	23.89	BIT / AGG	7.11	2.5	1.9	0.0		
1217+74.84	SD RD	RT	87.50	OIL & CHIP		4.9	7.0	0.2		3.0
1218+66.46	PE	LT	31.67	AGG		3.3	11.9	0.1		
1220+82.63	PE	RT	24.44	BIT / AGG	5.33	2.6	2.0	0.0		
1222+13.42	PE	RT	33.72	BIT / CONC	9.07	3.5	2.7	0.1		
1224+28.97	PE	RT	24.44	BIT / AGG	5.33	2.6	2.0	0.0		
1226+20.82	CE	RT	29.67	BIT / AGG	7.42	3.1	2.4	0.1		
1227+80.76	PE	LT	19.89	BIT	3.51	2.1	1.6	0.0		
1227+96.78	SD RD	RT	304.83	BIT	116.22	32.0	24.4	0.6	29.1	3.0
1228+20.54	SD RD	LT	141.83	AGG		14.9	53.2	0.3	6.9	3.0
MAILBOX TURNOUTS - 11 EACH			333.64			37.37	26.7			
TOTALS					876	378	446	7	175	48

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 3/22/2007
FILE NAME = c:\pr0jects\pb82001\details.dgn
PLOT SCALE = $SCALE$
USER NAME = schwenkberg