

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
41	(15)RS-3	LIVINGSTON	16	6
STA		TO STA		
FED ROAD DIST NO	ILLINOIS	FED AID PROJECT		

CONTRACT NO. 66421

MAINLINE SCHEDULE

LOCATION STA TO STA		LENGTH FOOT	RESURF AREA SQ YD	HMA SURF CSE, MIX "C", N70 TON	LEVEL BINDER (MM) TON	HMA SURF REM 3/4" SQ YD	HMA SURF REM 1 1/2" SQ YD	COLD MILL SQ YD	HMA SURF REM (BUTT JT) SQ YD	TEMP RAMP SQ YD	BIT MAT (PR CT) GALLON	AGG (PR CT) TON	MIX FOR CRACKS JTS & FLGWYS TON	LEVEL BINDER (HM) TON	HMA SHLD TON	AGG SHLD TON
-1+18 TO 4+44.40	CURB & GUTTER AREA AT IL 47	562.4	3654.7	307.0			3654.7			53.3	292	7.3	1.1	1.8		
4+44.40 TO 5+04.40	HMA TRANSITION	60	200.0	16.8	8.4	200.0		93.3			16	0.4	0.1	0.1		15.9
5+04.40 TO 8+74		369.6	1232.0	103.5	51.7	1232.0		574.9			99	2.5	0.4	0.6		98.2
8+74 TO 8+90	SN 053-2011 (BOX CULVERT)	16	53.3	4.5	2.2	53.3		24.9			4	0.1	0.0	0.0		4.3
8+90 TO 183+94.60		17504.6	58348.7	4901.3	2450.6	58348.7		27229.4			4668	116.7	17.5	29.2		4651.7
183+64.38 TO 184+24.38	BUTT JOINT	60	200.0	16.8	8.4	100.0		93.3	100.0	16.7	16	0.4	0.1	0.1		15.9
184+54.38 TO 185+84.40	OMISSION S.N. 053-0146															
185+84.40 TO 186+44.40	BUTT JOINT	60	200.0	16.8	8.4	100.0		93.3	100.0	16.7	16	0.4	0.1	0.1		15.9
186+44.40 TO 237+80		5135.6	17118.7	1438.0	719.0	17118.7		7988.7			1369	34.2	5.1	8.6		1364.7
237+80 TO 238+40	BUTT JOINT	60	200.0	16.8	8.4	100.0		93.3	100.0	16.7	16	0.4	0.1	0.1		15.9
238+40 TO 249+85	OMISSION S.N. 053-0147															
249+85 TO 250+45	BUTT JOINT	60	200.0	16.8	8.4	100.0		93.3	100.0	16.7	16	0.4	0.1	0.1		15.9
250+45 TO 302+73		5228	17426.7	1463.8	731.9	17426.7		8132.4			1394	34.9	5.2	8.7		1389.3
302+73 TO 309+34		661	1909.6	160.4	80.2	3231.6					259	6.5	0.6	1.6	166.6	
309+34 TO 321+42.47		1208.47	3491.1	293.3	146.6	3491.1					279	7.0	1.0	1.7		103.2
321+42.47 TO 322+02.47	BUTT JOINT	60	173.3	14.6	7.3	86.7			86.7	14.4	14	0.3	0.1	0.1		5.1
322+02.47 TO 324+39.61	OMISSION S.N. 053-0150															
324+39.61 TO 324+99.61	BUTT JOINT	60	173.3	14.6	7.3	86.7			86.7	14.4	14	0.3	0.1	0.1		5.1
324+99.61 TO 328+50		350.39	1012.2	85.0	42.5	1012.2					81	2.0	0.3	0.5		29.9
328+50 TO 342+00		1350	3900.0	327.6	163.8	6600.0					528	13.2	1.2	3.3	340.2	
342+00 TO 406+66.03		6466.03	18679.6	1569.1	784.5	18679.6					1494	37.4	5.6	9.3		552.3
406+66.03 TO 407+26.03	BUTT JOINT	60	173.3	14.6	7.3	86.7			86.7	14.4	14	0.3	0.1	0.1		5.1
407+26.03 TO 408+41.97	OMISSION S.N. 053-0151															
408+41.97 TO 409+01.97	BUTT JOINT	60	173.3	14.6	7.3	86.7			86.7	14.4	14	0.3	0.1	0.1		5.1
409+01.97 TO 428+00		1898.03	5483.2	460.6	230.3	5483.2					439	11.0	1.6	2.7		162.1
428+00 TO 428+60	BUTT JOINT	60	173.3	14.6	7.3	86.7			86.7	14.4	14	0.3	0.1	0.1		5.1
TOTAL				11271.1	5481.8	133710.6	3654.7	44416.8	833.5	192.1	11056	276.3	40.6	69.0	506.8	8460.7

OMISSIONS:

- SN 053-0146 - STA 184+54.38 TO 185+84.4
- SN 053-0147 - STA 238+40 TO 249+85
- SN 053-0150 - STA 322+02.47 TO 324+39.61
- SN 053-0151 - STA 407+26.03 TO 408+41.97

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

REVISIONS	
NAME	DATE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY