

PAVEMENT MARKING SCHEDULE									
STA TO STA	LOCATION	LENGTH FOOT	PAINT PVMT MARK WHITE 4"	PAINT PVMT MARK YELLOW 6"	THERMO PVMT MARK		THERMO PVMT MARK WHITE 8"	THERMO PVMT MARK WHITE 12"	THERMO PVMT MARK WHITE 24"
			FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
-1+18.00 TO 4+44.40	IL 47 & IL 17 INTERSECTION	562.40			173	615			136
4+44.40 TO 184+ 54.38		18009.98	36020	4502					
184+54.38 TO 185+84.40	OMISSION S.N. 053-0146								
185+84.40 TO 238+40		5255.60	10511	1314					
238+40 TO 249+85	OMISSION S.N. 053-0147								
249+85 TO 322+02.47		7217.47	14435	1804			180	60	60
322+02.47 TO 324+39.61	OMISSION S.N. 053-0150								
324+39.61 TO 407+26.03		8286.42	16573	2072					
407+26.03 TO 408+41.97	OMISSION S.N. 053-0151								
408+41.97 TO 428+30		1988.03	3976	497					
					173	615			
TOTAL			81515	10189	788		180	60	196

TEMPORARY PAVEMENT MARKING SCHEDULE									
STA TO STA	LOCATION	LENGTH FOOT	SHORT TERM PAVEMENT MARKING YELLOW	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING 4"	TEMPORARY PAVEMENT MARKING 6"	TEMPORARY PAVEMENT MARKING 8"	TEMPORARY PAVEMENT MARKING 12"	TEMPORARY PAVEMENT MARKING 24"
			FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT
-1+18.00 TO 4+44.40	IL 47 & IL 17 INTERSECTION		141	23		788			136
4+44.40 TO 184+ 54.38		18009.98	5403	1201	36020	4502			
184+54.38 TO 185+84.40	OMISSION S.N. 053-0146								
185+84.40 TO 238+40		5255.60	1577	350	10511	1314			
238+40 TO 249+85	OMISSION S.N. 053-0147								
249+85 TO 322+02.47		7217.47	2165	481	14435	1804	180	60	60
322+02.47 TO 324+39.61	OMISSION S.N. 053-0150								
324+39.61 TO 407+26.03		8286.42	2486	552	16573	2072			
407+26.03 TO 408+41.97	OMISSION S.N. 053-0151								
408+41.97 TO 428+30		1988.03	596	132	3976	497			
TOTAL			12368	2739	81515	10977	180	60	196

SEEDING SCHEDULE									
STA	SIDE	SIDEROAD OR DESCRIPTION	LENGTH	SEEDING CL 2	FURN EXC	EROSION CONTROL BLANKET	NIT FERT NUT	PHOS FERT NUT	POT FERT NUT
				ACRE	CU YD	SQ YD	LB	LB	LB
302+73 TO 309+34	RT	HMA SHLDR	661	0.076	11.5	367	7	7	7
302+73 TO 309+35	LT	HMA SHLDR	661	0.076	11.5	367	7	7	7
328+50 TO 342+00	RT	HMA SHLDR	1350	0.155	23.4	750	14	14	14
328+50 TO 342+01	LT	HMA SHLDR	1350	0.155	23.4	750	14	14	14
6+55	RT	JOHN ST		0.011	1.1	52	1	1	1
11+40	RT	BANNON ST		0.011	1.1	52	1	1	1
106+40	RT	2900 E RD (TR 244)		0.011	1.1	52	1	1	1
106+40	LT	2900 E RD (TR 244)		0.011	1.1	52	1	1	1
159+38	RT	3000 E RD (TR 250)		0.011	1.1	52	1	1	1
159+38	LT	3000 E RD (TR 250)		0.011	1.1	52	1	1	1
201+66	RT	3100 E RD (TR 262)		0.011	1.1	52	1	1	1
201+66	LT	3100 E RD (TR 262)		0.011	1.1	52	1	1	1
254+44	RT	3200 E RD (TR 268)		0.011	1.1	52	1	1	1
254+44	LT	3200 E RD (TR 268)		0.011	1.1	52	1	1	1
307+95	RT	3300 E RD (CAMPUS BLAIR RD)		0.011	1.1	52	1	1	1
307+95	LT	3300 E RD (CAMPUS BLAIR RD)		0.011	1.1	52	1	1	1
361+38	RT	3400 E RD (TR 27)		0.011	1.1	52	1	1	1
374+54	LT	3425 E RD (TR 280)		0.011	1.1	52	1	1	1
414+34	RT	3500 E RD (TR 282) RT		0.011	1.1	52	1	1	1
414+34	LT	3500 E RD (TR 282) RT		0.011	1.1	52	1	1	1
				0.638	87.4	3066	58	58	58

OMISSIONS:
 SN 053-0146 - STA 184+54.38 TO 185+84.4
 SN 053-0147 - STA 238+40 TO 249+85
 SN 053-0150 - STA 322+02.47 TO 324+39.61
 SN 053-0151 - STA 407+26.03 TO 408+41.97

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE