

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5952	Q-BR	GRUNDY	86	5
STA.		TO STA.		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE 0% CITY				
				ROADWAY 1000-2A	NETTLE CR. PR. 032-0107 EX. 032-0076 X071-2A	RETAINING WALL #1	RETAINING WALL #2 SN 032-8802	RETAINING WALL #3 SN 032-8803
44000700	APPROACH SLAB REMOVAL	SQ YD	150		150			
44004000	PAVED DITCH REMOVAL	FOOT	226	226				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	600	600				
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1783	1783				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1			
50105220	PIPE CULVERT REMOVAL	FOOT	62	62				
50200100	STRUCTURE EXCAVATION	CU YD	1731		260	178	283	1010
50300100	FLOOR DRAINS	EACH	10		10			
50300225	CONCRETE STRUCTURES	CU YD	1363.2		449.3	49.0	250.7	614.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	322.3		322.3			
50300260	BRIDGE DECK GROOVING	SQ YD	1620		1620			
50300300	PROTECTIVE COAT	SQ YD	2250		1871	119	50	210
50300510	RUSTICATION FINISH	SQ FT	6691				1900	4791
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1			
50500505	STUD SHEAR CONNECTORS	EACH	5956		5730	226		
* 50700209	UNTREATED TIMBER LAGGING	SQ FT	787			787		
50800105	REINFORCEMENT BARS	POUND	8950		8950			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	213780		117310	7620	24360	64490
50800515	BAR SPLICERS	EACH	804		804			
50901125	STEEL RAILING (TEMPORARY)	FOOT	117.5		117.5			
50901720	BICYCLE RAILING	FOOT	259			259		
51201400	FURNISHING STEEL PILES HP10X42	FOOT	792		792			
51202305	DRIVING PILES	FOOT	792		792			
51203400	TEST PILE STEEL HP10X42	EACH	2		2			
51204650	PILE SHOES	EACH	46		46			
51205200	TEMPORARY SHEET PILING	SQ FT	867		867			
51500100	NAME PLATES	EACH	1		1			
51602000	PERMANENT CASING	FOOT	133		133			
* 51603000	DRILLED SHAFT IN SOIL	CU YD	40		40			
* 51604000	DRILLED SHAFT IN ROCK	CU YD	4		4			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	183		183			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	30		30			
52100520	ANCHOR BOLTS, 1"	EACH	40		40			
52100530	ANCHOR BOLTS, 1 1/4"	EACH	20		20			
52100540	ANCHOR BOLTS, 1 1/2"	EACH	20		20			

\*SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
130 E. RANDOLPH STREET  
CHICAGO, ILLINOIS 60601  
JOB NO. 541



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 6  
SUMMARY OF QUANTITIES

SCALE: VERT. NTS  
HORIZ. NTS  
DATE 3/19/07

DRAWN BY RGR  
CHECKED BY DDM

In:\S\66594\66594.dwg 3/19/2007 3:26:04 PM  
 deFault