

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5952	Q-BR	GRUNDY	86	6
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

80% FEDERAL  
20% STATE  
0% CITY

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE 0% CITY					
				ROADWAY 1000-2A	NETTLE CR. PR. 032-0107 EX. 032-0076 X071-2A	RETAINING WALL #1	RETAINING WALL #2 SN 032-8802	RETAINING WALL #3 SN 032-8803	Y007
54213453	END SECTIONS 18"	EACH	1	1					
54213459	END SECTIONS 24"	EACH	4	4					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1					
55101200	STORM SEWER REMOVAL 24"	FOOT	317	317					
58700300	CONCRETE SEALER	SQ FT	510		510				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	1056		107	124	199	626	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	208	208					
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	1759		174	293	240	1052	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8	8					
60225400	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60226200	RESTRICTED DEPTH MANHOLES, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5					
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	8	8					
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2					
60255500	MANHOLES TO BE ADJUSTED	EACH	10	10					
60256400	MANHOLES TO BE ADJUSTED WITH NEW TYPE 8 GRATE	EACH	2	2					
60261000	INLETS TO BE ADJUSTED WITH NEW TYPE 8 GRATE	EACH	7	7					
60600097	CLASS S1 CONCRETE (OUTLET), SPECIAL	CU YD	1.5	1.5					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	30	30					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1112.5	1112.5					
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3					
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3					
63200310	GUARDRAIL REMOVAL	FOOT	805	805					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9					
67100100	MOBILIZATION	L SUM	1	1					
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2332	2332					
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	21070	21070					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6093	6093					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1712.5	1712.5					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	262.5	262.5					
* 70500690	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	2	2					
* 78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	5827	5827					
* 78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	183	183					
* 78008250	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	FOOT	531	531					

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 6  
SUMMARY OF QUANTITIES

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
130 E. RANDOLPH STREET  
CHICAGO, ILLINOIS 60601  
JOB NO. 541



SCALE: VERT. NTS  
HORIZ. NTS  
DATE 3/19/07

DRAWN BY RGR  
CHECKED BY DDM