

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5952	Q-BR	GRUNDY	86	7
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE 0% CITY				
				ROADWAY	NETTLE CR. PR. 032-0107 EX. 032-0076	RETAINING WALL #1	RETAINING WALL #2 SN 032-8802	RETAINING WALL #3 SN 032-8803
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	25	25				
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4				
78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	45	45				
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	826	826				
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	17	17				
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	425	425				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	116	116				
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	3	3				
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	59	59				
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	195	195				
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	321	321				
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	247	247				
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	400	400				
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	323	323				
X0320139	TEMPORARY CONSTRUCTION FENCE	FOOT	1755	1755				
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	2		2			
X0712400	TEMPORARY PAVEMENT	SO YD	2780	2780				
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION, LOCATION 1	EACH	1		1			
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION, LOCATION 2	EACH	1		1			
51202210	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	403			403		
XX006396	STORM SEWER DUCTILE IRON PIPE CLASS 52 36"	FOOT	26.4	26.4				
Z0001050	AGGREGATE SUBGRADE 12"	SO YD	4267	4267				
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4				
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2				
X0325751	DRIVING SOLDIER PILES	FOOT	403			403		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1				
70103015	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5				
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	44		44			
Z0076600	TRAINEES	Hour	1,000	1,000				

■ Y080  
\* SPECIALTY ITEM

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
130 E. RANDOLPH STREET  
CHICAGO, ILLINOIS 60601  
JOB NO. 541



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 6  
SUMMARY OF QUANTITIES

SCALE: VERT. NTS  
HORIZ. NTS  
DATE 3/19/07

DRAWN BY RGR  
CHECKED BY DDM