

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	-	IROQUOIS	17	9

•38(1,2,3,4,5,6,7,8,9)PATCHING

CLASS A PATCHING SCHEDULE													
LOCATION		PASSING LANE						DRIVING LANE					
MILE POST	LANE	TYPE II 11"	TYPE III 11"	TYPE IV 11"	PATCH REINF.	SAW CUTS	TIE BARS	TYPE II 11"	TYPE III 11"	TYPE IV 11"	PATCH REINF.	SAW CUTS	TIE BARS
		SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH
263.49	NB	FORD/IROQUOIS COUNTY LINE											
264.69	NB				8	60		16			16	72	
268.40	NB	8			8	60					8	60	
269.10	NB							8			8	60	
269.30	NB							8			8	60	
269.50	NB							8			8	60	
269.50	NB	8			8	60		8			8	60	
269.60	NB	8			8	60		8			8	60	
270.70	NB							11			11	64	
271.10	NB		16		16	72		13			13	68	
271.20	NB		16		16	72		8			8	60	
277.60	NB							8			8	60	
279.30	NB							11			11	64	
279.70	NB							8			8	60	
TOTAL		24	32	0	56	324		99	16		115	748	

CLASS A PATCHING SCHEDULE													
LOCATION		PASSING LANE						DRIVING LANE					
MILE POST	LANE	TYPE II 15"	TYPE III 15"	TYPE IV 15"	PATCH REINF.	SAW CUTS	TIE BARS	TYPE II 15"	TYPE III 15"	TYPE IV 15"	PATCH REINF.	SAW CUTS	TIE BARS
		SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH
281.90	NB	8			8	60		8		27	27	88	10
282.99	NB							8			8	60	
283.01	NB	8			8	60		8			8	60	
283.10	NB	8			8	60		8			8	60	
283.20	NB	8			8	60					8	60	
283.70	NB	8			8	60		8			8	60	
283.70	NB							8			8	60	
283.70	NB	8			8	60		8			8	60	
283.90	NB	8			8	60		8			8	60	
284.30	NB							8			8	60	
284.50	NB							8			8	60	
285.01	NB		16		16	72			16		16	72	
285.08	NB							8		16	8	60	
298.00	NB	8			8	60		8			8	60	
298.10	NB	11			11	64		11			11	64	
301.96	NB	IROQUOIS/KANKAKEE COUNTY LINE											
TOTAL		75	16		91	616		99	16	27	142	884	10

Date: MARCH 5, 2007  
c:/projects/cm307/details.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULES - PATCHING NBL**  
FAI ROUTE 57 (I-57)  
SECTION 38(1,2,3,4,5,6,7,8,9)PATCHING  
IROQUOIS COUNTY