

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	D4 1-74	PEORIA	21	2
74 Landscaping 2007				
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

GENERAL NOTES:

1. MICROSTATION AND GEOPAK FILES OF THIS PROJECT WILL BE MADE AVAILABLE TO THE CONTRACTOR. IF THERE IS A CONFLICT BETWEEN THE ELECTRONIC FILES AND THE PRINTED CONTRACT PLANS AND DOCUMENTS, THE PRINTED CONTRACT PLANS AND DOCUMENTS SHALL TAKE PRECEDENCE OVER THE ELECTRONIC FILES. THE CONTRACTOR SHALL ACCEPT ALL RISK ASSOCIATED WITH USING THE ELECTRONIC FILES AND SHALL HOLD THE DEPARTMENT HARMLESS FOR ANY ERRORS OR OMISSIONS IN THE ELECTRONIC FILES AND THE DATA CONTAINED THEREIN. ERRORS OR DELAYS RESULTING FROM THE USE OF THE ELECTRONIC FILES BY THE CONTRACTOR SHALL NOT RESULT IN AN EXTENSION OF TIME FOR ANY INTERIM OR FINAL COMPLETION DATE OR SHALL NOT BE CONSIDERED CAUSE FOR ADDITIONAL COMPENSATION. THE CONTRACTOR SHALL NOT USE, SHARE, OR DISTRIBUTE THESE ELECTRONIC FILES EXCEPT FOR THE PURPOSE OF CONSTRUCTING THIS CONTRACT. ANY CLAIMS BY THIRD PARTIES DUE TO USE OR ERRORS SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL INCLUDE THIS DISCLAIMER WITH THE TRANSFER OF THESE ELECTRONIC FILES TO ANY OTHER PARTIES AND SHALL INCLUDE APPROPRIATE LANGUAGE BINDING THEM TO SIMILAR RESPONSIBILITIES.

PROJECT SPECIFIC GENERAL NOTES:

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED), REFER ART. 107.31 FOR UTILITIES PROPERTIES AND SERVICES
2. THE CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. THE ACTUAL LOCATION OF PROPOSED LANDSCAPING SHALL BE ADJUSTED BY THE RESIDENT ENGINEER IN THE FIELD TO AVOID UTILITIES AND FIT FIELD CONDITIONS.
4. WHERE SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED THEIR LOCATION.
5. ALL PLANS ARE IN SCALE, FOR CONSTRUCTION DIMENSIONS THE CONTRACTOR NEED TO VERIFY ON SITE.
6. REMOVAL OF UNDERBRUSH, DEBRIS OR OTHER MISCELLANEOUS ITEMS TO ALLOW THE PLACEMENT OF LANDSCAPING ITEMS SHALL BE INCLUDED IN THE PRICE OF THE ASSOCIATED PAY ITEMS.
7. THE CONTRACTOR SHALL USE CARE IN GRADING OR EXCAVATING NEAR ANY AND ALL EXISTING ITEMS WHICH WILL NOT BE REMOVED. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE.
8. INTERSEEDING, CLASS 2A AND MULCH, METHOD 2 LOCATIONS WILL BE SELECTED BY THE RESIDENT ENGINEER BASED ON CONDITIONS OF EXISTING TURF.
9. CONTROL ALL INVASIVE WEED SPECIES FOUND IN THE CLASS 4A AND CLASS 5 SEEDING AREAS AS DIRECTED BY THE ENGINEER. THE CONTROL IN SUCH AREAS SHALL BE COMPLETED AT THE TIME OF THE PHASE I, II, III, AND IV COMPLETION DATES. IF NOT COMPLETED AT EACH COMPLETION DATE, THE COMPLETION OF THAT PHASE WILL NOT BE ACCEPTED AND WILL RESULT IN A "FAILURE TO COMPLETE LANDSCAPE CONSTRUCTION AND LANDSCAPE ESTABLISHMENT WORK" AND BE CHARGED ACCORDINGLY.

COMMITMENTS:

COMMITMENTS SHALL NOT BE ALTERED WIHTOUT WRITTEN APPROVAL OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE

NO COMMITMENTS HAVE BEEN INCURRED ON THIS PROJECT.

STATUS OF UTILITIES:

NO UTILITIES ARE TO BE RELOCATED FOT THIS PROJECT. THE CONTRACTOR SHALL CONTACT JULIE AND IDOT PRIOR TO ANY EXCAVATION.

ALL IDOT UTILITES WILL BE LOCATED BY "OTHERS".

STANDARDS LIST:

- 202001 EARTH MEDIAN DITCH CHECK
- 280001-03 TEMPORARY EROSION CONTROL SYSTEM
- 602401-01 MANHOLE TYPE A
- 202001 EARTH MEDIAN DITCH CHECK
- 604001-02 FRAME AND LIDS, TYPE 1
- 701106-01 OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 4.5 m (15') AWAY, FOR SPEEDS > 45 MPH
- 701101-01 OFF-ROAD OPERATIONS, MULTILANE LESS THAN 4.5 m (15') AWAY FOR SPEEDS > 45 MPH
- 701201-02 LANE CLOSURE , 2L, 2W, DAY ONLY ON-ROAD TO 600mm OFF FOR SPEEDS > 45 MPH
- 701400-02 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701406-04 LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY FOR SPEEDS > 45 MPH
- 701411-03 LANE CLOSURE, MULTILANE AT ENTRANCE OR EXIT RAMP FOR SPEEDS > 45 MPH
- 701426-02 LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER. FOR SPEEDS > 45 MPH
- 701502-01 URBAN LANE CLOSURE 2L, 2W, WITH BIDIRECTIONAL LEFT TURN LANE
- 701601-04 URBAN LANE CLOSURE, MULTILANE 1W OR 2W WITH NONTRAVERSABLE MEDIAN
- 701602-02 URBAN LANE CLOSURE, MULTILANE 2W WITH BIDIRECTIONAL LEFT TURN LANE
- 701606-04 URBAN LANE CLOSURE, MULTILANE 2W WITH MOUNTABLE MEDIAN
- 702001-06 TRAFFIC CONTROL DEVICES



REVISIONS	
NAME	DATE
FINAL PLAN	05/11/04
PREFINAL PLAN	03/01/04
PRELIMINARY	11/17/03

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 74 (I-74)
 GENERAL NOTES,
 STANDARDS AND
 COMMITMENTS
 DATE: 07/16/2004
 DRAWN BY: KC/DL
 CHECKED BY: JB