

| | | | | |
|---|----------|----------|--------------|-----------|
| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 2466 | (11RS-3) | WOODFORD | 23 | 5 |
| FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT | | | | |

| SUMMARY OF QUANTITIES | | | | | 80% FED 20% STATE |
|-----------------------|--|--------|----------------|---------|----------------------|
| | | | | | INTERSTATE ROADWAY |
| CODE NO. | PAY ITEM | UNIT | TOTAL QUANTITY | 1000 | |
| 40600215 | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) | TON | 60.4 | 60.4 | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 237 | 237 | |
| X4067107 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 4,650 | 4,650 | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 7,728 | 7,728 | |
| 40600990 | TEMPORARY RAMP | SQ YD | 484 | 484 | |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 9,322 | 9,322 | |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 813 | 813 | |
| 44000155 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SQ YD | 110,079 | 110,079 | |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 1,238 | 1,238 | |
| 44201803 | CLASS D PATCHES, TYPE II, 13 INCH | SQ YD | 772 | 772 | |
| 44201807 | CLASS D PATCHES, TYPE III, 13 INCH | SQ YD | 211 | 211 | |
| 44201809 | CLASS D PATCHES, TYPE IV, 13 INCH | SQ YD | 224 | 224 | |
| 44300200 | STRIP REFLECTIVE CRACK CONTROL TREATMENT | FOOT | 44,563 | 44,563 | |
| 66700205 | PERMANENT SURVEY MARKERS, TYPE 1 | EACH | 4 | 4 | |
| 66700605 | PERMANENT SURVEY TIES | EACH | 16 | 16 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 3 | 3 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |

SUMMARY OF QUANTITIES